

narca

# Holliston Wastewater Treatment Plant Modernization Immediate Modernization Recommendations

Holliston Historical Society Holliston Police Department Miller Elementary School

Sam Placent no Elementary School

Linden St

Flagg Field

Damigella Field

Halliston Oil Service

Robert Adams Micdle School

Next Generation Martia

Timothy Daniels House Rehabilitation &

Elm St

Shurchist

A Party Street

Church St Ms. Rebecca Morgan

Holliston Public Library

Iolliston Superette

aspenituliika

Holliston Rail Trail

asey's Pub

Submitted to: Town of Holliston 703 Washington Street Holliston, MA 01746 **Environmental Engineers/Consultants** 

LOMBARDO ASSOCIATES, INC.

Sentral

September 23, 2022

188 Church Street, Newton, Massachusetts 02458

# TABLE OF CONTENTS

1	INTRODUCTION	3
2	IMMEDIATE MODERNAZATION RECOMMENDATIONS	6
	TABLE OF FIGURES	

Figure 1-1 Holliston WWTP Process Flow Diagram	3
Figure 1-2 WWTF Plan View # 1	4
Figure 1-3 WWTF Plan View # 2	5

#### TABLE OF TABLES

Table 2-1 Immediate Modernization Recommendations	6
Table 2-2 Capital Cost Budgets – Equipment / Work Details	7
Table 2-3 Capital Cost Budget & Basis	8

<u>Authorization</u>: The Town of Holliston retained Lombardo Associates, Inc. to perform Wastewater Treatment Plant Modernization And Downtown Sewer Connectivity Analysis. This Report presents the Immediate Modernization Recommendations for the Wastewater Treatment Plant. Additional Project Reports will be issued on:

- ✓ Capacity of the Wastewater System to process and discharge wastewater from the Downtown Sewer Area,
- ✓ Downtown Sewering Options
- ✓ Additional Modernization Recommendations,
  - Resulting from ongoing data treatment plant collection and analysis

# **1** INTRODUCTION

This Report addresses the immediate process modifications / improvements needed to:

- 1. Address essential facility modernizations for the 20+ year old Holliston Woodland Street School Complex Wastewater System and Wastewater Treatment Facility (WWTF)
- 2. Improve the ability of the existing treatment system to achieve permit compliance.

Figure 1-1 presents the process flow diagram of the complete Woodland School wastewater system and the details of the WWTF components.



# Figure 1-1 Holliston WWTP Process Flow Diagram

Figure 1-2 presents a WWTF plan view. Figure 1-3 illustrate flow direction of wastewater, recycle and air.



# Figure 1-2 WWTF Plan View # 1





# 2 IMMEDIATE MODERNAZATION RECOMMENDATIONS

A summary of the WWTF Immediate Improvement recommendations is presented on Table 2-1, with details presented on Table 2-2.

The proposed WWTF Immediate Improvement Recommendations Capital Cost budget is presented on Table 2-3. Capital cost line-item budgets are interdependent. Consequently, removing an item does not necessarily result in the same net total cost reduction.

	Item	Solution		
1	Influent Splitter Box Replacement	Replace Flow Splitter Box - with weir		
2	Influent Flow Measurement	Add an ultrasonic level transducer to the Flow Control Box.		
3	Alkalinity Feed System Addition	Add automatic feed system, feed based upon flow		
4	Remote Monitoring and Control System	Budget Allowance		
-	Process Piping Improvements	Extend 2 recycle lines to influent of Biofilter #1,		
5		permenant solution to series connection		
6	Anoxic mixer / baffle wall	Mixing / settling improvements		
7	Effluent Flow Measurement	Extend platform past UV unit, add weirbox + ultrasonic		
8	Analytical Equipment for Process Performance Monitoring	Obtain new Benchtop Photometer, accessories and reagents to allow for benchtop ammonia, nitrate, pH and Alkalinity analyses		
9	ISE Ammonia / Nitrate - ORP	Continuous performance monitoring		
10	Composite Sampler	Permit Required		
11	Miscellaneous Facility Cleaning/Painting	Sand blast and paint corroded areas		
12	Spare Parts			
13	Intensive Process Data Collection	Weekly data collection to identify process adjustments / improvements for permit compliance		

#### Table 2-1 Immediate Modernization Recommendations

ltem #	Item Description / List				
1	Splitter Box Replacement				
2	Influent Flow Measurement				
3	Alk Feed Equip				
3.1	Tank				
3.2	Mixer				
3.3	Pump				
3.4	Level sensor				
3.5	SCADA connection				
4	Remote Monitoring & Control-SCADA				
5	Process Piping Improvements				
5.1	Series connect Biofilter #1 to Biofilter #2				
5.2	Extend recycle line to inlet end of				
	Biofilter #1				
5.3	Extend recycle line from Biofilter #3 to				
	Inlet of Biofilter #1				
6	Anovia miyor / haffla wall				
7	Effluent Flow Measurement				
0	Analytical Equipment				
0 Q 1	Renchton analyzer				
8.1	Beagents				
83	Mise Fauin				
0.5					
9	ISE Ammonia / Nitrate - ORP				
10	Composite Sampler				
11	Miscellaneous Facility Cleaning/Painting				
12	Spare Parts				
12.1	Flow EO pump				
12.2	Recycle Pump				
12.3	Dosing Pump				
12.4	Anoxic Mixer				
12.5	SCADA I/O Modules				
12.6	Ultrasonics				
12.7	Nitrate / Ammonia Analyzers cartridges				
12.8	Air Valves				
12.9	Collection System Pumps & Floats				
12.91	Miscellaneous				

Table 2-2 Capital Cost Budgets – Equipment / Work Details

Construction Budget				Eng	Total
Equipment	E Co	Est. Total Construction Costs		. Design E + Start	Est. Capital Costs
Splitter Box	\$	15,600	\$	2,840	\$ 18,440
Ultrasonic Level Transducer	\$	7,200	\$	3,450	\$ 10,650
Alk	\$	22,080	\$	4,390	\$ 26,470
SCADA	\$	107,000	\$	26,400	\$133,400
Piping	\$	13,200	\$	6,640	\$ 19,840
Anox. Mixing	\$	18,000	\$	3,840	\$ 21,840
Effl Flow	\$	30,000	\$	6,930	\$ 36,930
Analytical Equip	\$	8,160	\$	3,400	\$ 11,560
Instruments	\$	45,600	\$	5,570	\$ 51,170
Sampler	\$	12,000	\$	2,550	\$ 14,550
Misc	\$	48,000	\$	8,840	\$ 56,840
Spare Parts	\$	42,000	\$	3,600	\$ 45,600
Process Data Collection	\$	1,000	\$	19,760	\$ 20,760
Subtotals	\$	354,240	\$	95,370	\$449,610

Table 2-3 Capital Cost Budget & Basis