



**2021**

**WATER SUPPLY  
AND WATER MAIN  
IMPROVEMENTS  
PLANNING**

**Holliston, Massachusetts**  
December 2021





# TABLES

| Table No. | Description  | Page |
|-----------|--|------|
| 1.        | US Census Historical Population – Town of Holliston .....                        | 7    |
| 2.        | Finished Water Use Categories .....  | 8    |
| 3.        | Historical Water Use – Million Gallons per Year (MGY)<br>.....                   | 9    |
| 4.        | Historical Water Use – Million Gallons per Year<br>(MGD) .....                   | 10   |
| 5.        | Historical Water Usage by User Class as Percent of<br>Annual Water Produced..... | 10   |
| 6.        | Historical Daily Residential Gallons per Capita Water<br>Demand.....             | 11   |
| 7.        | Historical Maximum and Average Day Demands.....                                  | 12   |
| 8.        | MRPC Population Projection Estimate .....  | 14   |
| 9.        | UMDI Population Projection Estimate.....   | 14   |
| 10.       | Stantec Population Projections.....  | 15   |
| 11.       | Projected Percentage Average Day Demand by<br>Use Category .....                 | 17   |
| 12.       | Projected Average Day Demand (MGY) by Use<br>Category .....                      | 17   |
| 13.       | Projected Average Day Demand (MGD) by Use<br>Category .....                      | 17   |
| 14.       | Projected Maximum and Average Day Demands .....                                  | 18   |
| 15.       | Approved Daily Pumping Rate (MGD) for each Well<br>.....                         | 22   |
| 16.       | Monthly Volume (MG) of Water Pumped from Well<br>2136000-01G.....                | 24   |
| 17.       | Monthly Volume (MG) of Water Pumped from Well<br>2136000-02G.....                | 25   |
| 18.       | Monthly Volume (MG) of Water Pumped from Well<br>2136000-04G.....                | 26   |
| 19.       | Monthly Volume (MG) of Water Pumped from Well<br>2136000-05G.....                | 27   |



| <b>Table No.</b> | <b>Description</b>  | <b>Page</b> |
|------------------|---|-------------|
| 20.              | Monthly Volume (MG) of Water Pumped from Well<br>2136000-06G..... | 28          |
| 21.              | Monthly Volume (MG) of Water Pumped from Well<br>2136000-07G..... | 29          |
| 22.              | Monthly Volume (MG) of Water Pumped from Well<br>2136000-08G..... | 30          |
| 23.              | Maximum Authorized Raw Water Withdrawal<br>Volumes per WMA.....   | 31          |
| 24.              | PCI Treatment Band Ranges.....                                    | 41          |
| 25.              | Zero Budget – Impact on Backlog .....                             | 52          |
| 26.              | Anticipated Budget – Impact on Backlog .....                      | 53          |

# FIGURES

| Figure No. | Description   | Page |
|------------|---|------|
| 1.         | Historical Population – Town of Holliston .....                   | 8    |
| 2.         | Metered Water Consumption in 2020.....                            | 9    |
| 3.         | Historical and Projected Population Trends .....                  | 15   |
| 4.         | Average Well Production Rate (MGD) per Year .....                 | 23   |
| 5.         | Monthly Volume (MG) of Water Pumped from Well<br>2136000-01G..... | 24   |
| 6.         | Monthly Volume (MG) of Water Pumped from Well<br>2136000-02G..... | 25   |
| 7.         | Monthly Volume (MG) of Water Pumped from Well<br>2136000-04G..... | 26   |
| 8.         | Monthly Volume (MG) of Water Pumped from Well<br>2136000-05G..... | 27   |
| 9.         | Monthly Volume (MG) of Water Pumped from Well<br>2136000-06G..... | 28   |
| 10.        | Monthly Volume (MG) of Water Pumped from Well<br>2136000-07G..... | 29   |
| 11.        | Monthly Volume (MG) of Water Pumped from Well<br>2136000-08G..... | 30   |
| 12.        | Typical Asset Management Deterioration Curve.....                 | 37   |
| 13.        | Pipe Segment Analysis .....                                       | 42   |
| 14.        | Town-wide Pipe Distribution in Miles by Repair<br>Activity .....  | 44   |
| 15.        | Pipe Distribution in Miles by Year Installed .....                | 45   |
| 16.        | Map of Town-wide Pipe Age .....                                   | 46   |
| 17.        | Dollar Backlog of Outstanding Repairs.....                        | 48   |
| 18.        | Map of Town-wide Backlog .....                                    | 49   |
| 19.        | Summary of Water Main Funding Scenarios .....                     | 54   |



# 1 INTRODUCTION

# 1. INTRODUCTION

## BACKGROUND

The Town of Holliston is located in Middlesex County, southwest of Boston, Massachusetts east of I-495. The Town of Holliston's water system consists of five active wells that provide an average of approximately 1.0 million gallons per day (MGD) of water to its almost 15,000 residents. The water is delivered from the well supplies to the customers through approximately 90 miles of 4-inch to 16-inch water mains. There are five (5) storage tanks with a total capacity of 5.6 million gallons that are used to maintain operating pressures and to provide fire protection.

The purpose of this study is to evaluate both the water supply and water distribution system to identify necessary improvements for a 20-year planning horizon.

The first component is to evaluate the Town of Holliston's current sources of water, and identify any anticipated shortfalls in supply over a 20-year planning horizon. Permitting and constructing new water supply sources can take many years to be approved, therefore completing a planning level evaluation will identify if there are future water supply needs for the Town or if current sources remain sufficient.

The second component is to update the Town of Holliston's water main replacement program. An Asset Management (AM) program for its water distribution system was originally developed in 2010. The Town has been working to address the recommendations in that 2010 plan and requested an update to the plan. This water main replacement plan has been coordinated with a recent Sidewalk and ADA compliance report completed by Stantec along with other studies related to Complete Streets and the Town's annual paving program.

This report is designed to be a network level - planning tool and intended to provide a foundation for managing the Town's water system resources by combining technology, local knowledge, and professional engineering input.



# 2 HISTORICAL DATA

# 2. WATER SUPPLY SYSTEM HISTORICAL DATA

## POPULATION

In evaluating Holliston’s water requirements, both present and future populations must be accounted for. Table 1 shows historical population data from 2000 to 2020, provided by the US Census Bureau. With the exception of the years 2002, 2003, 2004, 2005, and 2010, the population of Holliston has experienced an overall upward trend since the 2000s.


**Table 1**  
**US Census Historical Population – Town of Holliston**

| Year | US Census Population | Percentage Change | Year | US Census Population | Percentage Change |
|------|----------------------|-------------------|------|----------------------|-------------------|
| 2000 | 13,864               | –                 | 2011 | 13,875               | 1.95%             |
| 2001 | 13,980               | 0.84%             | 2012 | 14,056               | 1.30%             |
| 2002 | 13,951               | -0.21%            | 2013 | 14,197               | 1.00%             |
| 2003 | 13,946               | -0.04%            | 2014 | 14,406               | 1.47%             |
| 2004 | 13,908               | -0.27%            | 2015 | 14,506               | 0.69%             |
| 2005 | 13,852               | -0.40%            | 2016 | 14,597               | 0.63%             |
| 2006 | 13,862               | 0.07%             | 2017 | 14,748               | 1.03%             |
| 2007 | 13,902               | 0.29%             | 2018 | 14,939               | 1.30%             |
| 2008 | 13,983               | 0.58%             | 2019 | 14,946               | 0.05%             |
| 2009 | 14,172               | 1.35%             | 2020 | 14,996               | 0.33%             |
| 2010 | 13,610               | -3.97%            |      |                      |                   |

Source: DataCommons.org

The data in Table 1 shows that the population of Holliston has gradually increased at an average rate of 0.4% from 2000 to 2020. Figure 1 shows this historical population information graphically.

**Figure 1**  
**Historical Population – Town of Holliston**



## WATER DEMAND

### Water Use Categories

Water consumption is typically comprised of residential, commercial, and industrial demands as well as Confidently Estimated Municipal Use (CEMU) and Unaccounted-for Water (UAW). A description of demand types is provided in Table 2.


**Table 2**  
**Finished Water Use Categories**

| <u>Use Category</u>                     | <u>Category Description</u>  |
|---|--|
| Residential                             | Water used in residences and apartments  |
| Residential Institutions                | Water used in residential establishments such as colleges  |
| Commercial/Business                     | Water used in restaurants, service stations, and retail establishments   |
| Agricultural                            | Water used for growing crops, raising animals, and/or running a garden center  |
| Industrial                              | Water used in manufacturing and warehousing facilities   |
| Municipal/ Institutional<br>Non-profits | Water used for municipal purposes, including schools, playing fields, municipal buildings, treatment plant; non-profits e.g. churches; non-residential institutions e.g. private schools                             |
| Other                                   | Water used for purposes not included in above categories   |
| CEMU                                    | Water Confidently Estimated for Municipal Use (e.g. fire protection and training, hydrant/water main flushing, flow testing, bleeders/blow offs, tank overflow and drainage, sewer system flushing, street cleaning) |
| UAW                                     | Unaccounted for Water - Water that includes all unmetered uses (e.g. leaks, and water main breaks, fire flows)   |

## Metered Finished Water Use

As presented in its 2020 Annual Statistical Report (ASR), the Holliston Water Department has 4,917 service connections; of which 4,649 are residential connections, 216 are commercial/business connections, 11 are agricultural connections, 20 are municipal/institutional/nonprofits, and 21 are other connections i.e. to churches in Town. Figure 2 presents the average metered water consumption by user classification in 2020. Most of the metered water use is residential, followed by commercial/business, residential institution, municipal/institutional/non-profits, industrial, and agricultural. CEMU and UAW volumes are not metered and therefore not included in the figure.

**Figure 2**  
**Metered Water Consumption in 2020**



## Historical Water Usage

Table 3 and Table 4. illustrate the historical annual water usage by user class for years 2009 through 2020, and Table 5 illustrates the historical total water usage by user class as a percentage of annual water consumed for the same timeframe. Note that ASR data for the years 2011 and 2013 were not available for analysis.

**Table 3**  
**Historical Water Use – Million Gallons per Year (MGY)**

| Year | Residential | Commercial/<br>Business | Agricultural | Industrial | Municipal/Institutional/<br>Non-profits | Other | Total<br>CEMU | UAW  | Total |
|------|-------------|-------------------------|--------------|------------|---|-------|---------------|------|-------|
| 2009 | 248.6       | 25.2                    | 0.7          | –          | 3.4                                     | 3.9   | 36.6          | 70.3 | 388.7 |
| 2010 | 249.3       | 23.7                    | 1.1          | –          | 3.7                                     | 2.3   | 13.6          | 50.9 | 344.8 |
| 2012 | 242.6       | 22.3                    | 1.0          | –          | 3.5                                     | 2.7   | 5.1           | 48.5 | 325.7 |
| 2014 | 238.7       | 23.6                    | 1.4          | –          | 3.4                                     | 2.3   | 54.3          | 60.7 | 384.4 |
| 2015 | 246.4       | 24.6                    | 0.9          | –          | 5.4                                     | 2.8   | 46.1          | 23.9 | 350.1 |
| 2016 | 235.9       | 22.5                    | 1.3          | –          | 12.1                                    | 0.2   | 41.1          | 47.6 | 360.6 |
| 2017 | 298.6       | 20.0                    | 1.1          | –          | 7                                       | 2.1   | 19.7          | 38.4 | 386.9 |
| 2018 | 230.0       | 21.3                    | 1.2          | –          | 10.6                                    | 2.3   | 48.3          | 74.5 | 388.1 |
| 2019 | 220.0       | 24.0                    | 1.3          | –          | 10.5                                    | 1.7   | 77.0          | 30.5 | 365.0 |
| 2020 | 249.0       | 2.2                     | 10.6         | –          | 8.6                                     | 18.9  | 26.1          | 24.6 | 340.0 |
| AVG  | 245.9       | 20.9                    | 2.1          | –          | 6.8                                     | 3.9   | 36.8          | 47.0 | 363.4 |



**Table 4**  
**Historical Water Use – Million Gallons per Year (MGD)**

| Year | Residential | Commercial/<br>Business | Agricultural | Industrial | Municipal/Institutional/<br>Non-profits | Other | Total<br>CEMU | UAW   | Total |
|------|-------------|-------------------------|--------------|------------|---|-------|---------------|-------|-------|
| 2009 | 0.681       | 0.069                   | 0.002        | –          | 0.009                                   | 0.011 | 0.100         | 0.193 | 1.06  |
| 2010 | 0.683       | 0.065                   | 0.003        | –          | 0.010                                   | 0.006 | 0.037         | 0.140 | 0.94  |
| 2012 | 0.663       | 0.061                   | 0.003        | –          | 0.010                                   | 0.007 | 0.014         | 0.133 | 0.89  |
| 2014 | 0.654       | 0.065                   | 0.004        | –          | 0.009                                   | 0.006 | 0.149         | 0.166 | 1.05  |
| 2015 | 0.675       | 0.067                   | 0.002        | –          | 0.015                                   | 0.008 | 0.126         | 0.066 | 0.96  |
| 2016 | 0.644       | 0.061                   | 0.004        | –          | 0.033                                   | 0.001 | 0.112         | 0.130 | 0.99  |
| 2017 | 0.818       | 0.055                   | 0.003        | –          | 0.019                                   | 0.006 | 0.054         | 0.105 | 1.06  |
| 2018 | 0.630       | 0.058                   | 0.003        | –          | 0.029                                   | 0.006 | 0.132         | 0.204 | 1.06  |
| 2019 | 0.603       | 0.066                   | 0.004        | –          | 0.029                                   | 0.005 | 0.211         | 0.083 | 1.00  |
| 2020 | 0.680       | 0.006                   | 0.029        | –          | 0.023                                   | 0.052 | 0.071         | 0.067 | 0.93  |
| AVG  | 0.673       | 0.057                   | 0.006        | –          | 0.019                                   | 0.011 | 0.101         | 0.129 | 0.99  |

**Table 5**  
**Historical Water Usage by User Class as Percent of Annual Water Produced**

| Year | Residential | Commercial/<br>Business | Agricultural | Industrial | Municipal/Institutional/<br>Non-profits | Other | Total<br>CEMU | UAW   | Total |
|------|-------------|-------------------------|--------------|------------|---|-------|---------------|-------|-------|
| 2009 | 64.0%       | 6.5%                    | 0.2%         | –          | 0.9%                                    | 1.0%  | 9.4%          | 18.1% | 100%  |
| 2010 | 72.3%       | 6.9%                    | 0.3%         | –          | 1.1%                                    | 0.7%  | 4.0%          | 14.8% | 100%  |
| 2012 | 74.5%       | 6.8%                    | 0.3%         | –          | 1.1%                                    | 0.8%  | 1.6%          | 14.9% | 100%  |
| 2014 | 62.1%       | 6.1%                    | 0.4%         | –          | 0.9%                                    | 0.6%  | 14.1%         | 15.8% | 100%  |
| 2015 | 70.4%       | 7.0%                    | 0.3%         | –          | 1.5%                                    | 0.8%  | 13.2%         | 6.8%  | 100%  |
| 2016 | 65.4%       | 6.2%                    | 0.4%         | –          | 3.3%                                    | 0.1%  | 11.4%         | 13.2% | 100%  |
| 2017 | 77.2%       | 5.2%                    | 0.3%         | –          | 1.8%                                    | 0.5%  | 5.1%          | 9.9%  | 100%  |
| 2018 | 59.3%       | 5.5%                    | 0.3%         | –          | 2.7%                                    | 0.6%  | 12.4%         | 19.2% | 100%  |
| 2019 | 60.3%       | 6.6%                    | 0.4%         | –          | 2.9%                                    | 0.5%  | 21.1%         | 8.3%  | 100%  |
| 2020 | 73.2%       | 0.6%                    | 3.1%         | –          | 2.5%                                    | 5.6%  | 7.7%          | 7.2%  | 100%  |
| AVG  | 67.9%       | 5.7%                    | 0.6%         | –          | 1.9%                                    | 1.1%  | 10.0%         | 12.8% | 100%  |

The increase in percentage use for residential and the significant decrease in percentage use for commercial/business between 2019 and 2020 could be attributed to the COVID-19 pandemic which saw a considerable number of people confined to their residences even for work hours. The high CEMU percentage use in 2019 was mainly due hydrant/water main flushing/main construction and bleeders/blowoffs. The elevated UAW percentage use in 2018 could be due to meter malfunctions/misregistrations, service leaks, and hydrant malfunctions. It is anticipated that the percentage for each user type is likely to remain similar to its historical 10-year average for the duration of the planning period, but should be revisited if significantly large users are added to the water system.

## Confidently Estimated Municipal Use and Unaccounted for Water

CEMU is the amount of water quantified by the Holliston Water department in its ASRs for purposes such as fire protection, hydrant flushing, bleeders/blow offs, source meter calibration adjustments, construction uses, and major water main breaks.

Unaccounted-for water (UAW) is often difficult to quantify. It typically consists of unmetered water usage such as leaks, water theft, or meter malfunction/misregistration. It is calculated by subtracting the sum of the total metered water usage and total CEMU from the total finished water produced and available for distribution.

UAW has averaged 12.8% over the study period, and have been lower than the 10% or less performance standard required by the Holliston Water Department's Water Management Act (WMA) registration permit for the past two years, i.e. in 2019 and 2020. Stantec assumes that the Holliston Water Department will continue to implement strategies to meet this requirement throughout the planning period.

## Domestic Water Consumption

Population, zoning, and water consumption habits collectively influence the pattern of domestic (residential) water use. Since consumption is primarily dependent on the population served, domestic water consumption is often expressed in terms of gallons per capita per day (GPCD). Table 6 illustrates the daily residential consumption per capita for years 2009 through 2020.

**Table 6**  
**Historical Daily Residential Gallons per Capita Water Demand**

| Year    | Daily Residential Water Use <sup>(1)</sup><br>(GPD) | Estimated Population<br>Served <sup>(2)</sup> | Residential Gallons per<br>Capita per Day (RGPCD) |
|---------|---|---|---|
| 2009    | 681,123   | 14,172  | 48.1  |
| 2010    | 683,131   | 13,610  | 50.2  |
| 2012    | 662,938   | 14,056  | 47.2  |
| 2014    | 654,038   | 14,406  | 45.4  |
| 2015    | 675,045   | 14,506  | 46.5  |
| 2016    | 644,443   | 14,597  | 44.1  |
| 2017    | 818,167   | 14,748  | 55.5  |
| 2018    | 630,137   | 14,939  | 42.2  |
| 2019    | 602,740   | 14,946  | 40.3  |
| 2020    | 680,328   | 14,996  | 45.4  |
| AVERAGE | 673,209   | 14,498  | 46.5  |

<sup>(1)</sup> As presented in the Holliston Water Department's past ASRs

<sup>(2)</sup> Per US Census data

Consumption rates varied from 40.3 to 55.5 residential gallons per capita per day (RGPCD) with an average of approximately 46.5 RGPCD. With the exception of year 2017, residential water use has remained fairly stable over this time period. Stantec assumes that the Town will continue its conservation efforts to stay below the RGPCD performance standard of 65 gallons for public water suppliers (PWS) permittees established by Massachusetts under the Water Management Act.

### Maximum Daily Demand

The maximum day demand is the largest volume of water used over a single 24-hour period. The ratio of maximum to average daily consumption is generally higher for residential use than it is for industrial and commercial use. Consumers can easily double or triple their average daily consumption by activities such as lawn watering, car washing, and swimming pool use. The maximum day demand from 2020 was 1.57 MGD per the ASR of that year. Table 7 provides a summary of the historical maximum day demand, average day demand and maximum day to average day ratio.

**Table 7**  
**Historical Maximum and Average Day Demands**

| <u>Year</u> | <u>Maximum Day Demand (MGD)</u> | <u>Average Day Demand (MGD)</u> | <u>Maximum Day to Average Day Ratio</u> |
|-------------|---------------------------------|---------------------------------|---|
| 2009        | 1.959                           | 1.065                           | 1.84                                    |
| 2010        | *                               | 0.945                           | -                                       |
| 2012        | 1.507                           | 0.890                           | 1.69                                    |
| 2014        | 1.879                           | 1.053                           | 1.78                                    |
| 2015        | 1.914                           | 0.959                           | 2.00                                    |
| 2016        | 1.605                           | 0.985                           | 1.63                                    |
| 2017        | 1.729                           | 1.060                           | 1.63                                    |
| 2018        | 1.591                           | 1.063                           | 1.50                                    |
| 2019        | 1.602                           | 1.000                           | 1.60                                    |
| 2020        | 1.461                           | 0.929                           | 1.57                                    |
| AVERAGE     | 1.661                           | 0.987                           | 1.68                                    |

\*Data not available



**3**  
**PROJECTIONS**

# 3. PROJECTIONS

## FUTURE POPULATION

Evaluation of the Town’s water supply and distribution system must consider future as well as present populations. Any increase in population affects the water supply and distribution needs. The majority of the Town’s population is served by the municipal water system operated by the Holliston Water Department and was assumed to be 100% for this evaluation.

The Metropolitan Area Planning Council (MAPC) uses a dynamic model to make population projections in the Greater Boston Region that are referenced by local, regional, and state agencies when establishing policies and investments to meet the needs of the region. The MAPC population projections developed for Holliston for the years 2020, 2030, and 2040 are shown in Table 8.

**Table 8**  
**MRPC Population Projection Estimate**

| Year                | 2020   | 2030   | 2040   |
|---------------------|--------|--------|--------|
| Population Estimate | 13,547 | 13,080 | 12,836 |

The UMass Donahue Institute (UMDI) produces population projections for Massachusetts regions and municipalities, which are referenced by planners and researchers. The UMDI population projections developed for Sterling for the years 2020, 2025, 2030, 2035, and 2040 are shown in Table 9.


**Table 9**  
**UMDI Population Projection Estimate**

| Year                | 2020   | 2025   | 2030   | 2035   | 2040   |
|---------------------|--------|--------|--------|--------|--------|
| Population Estimate | 13,170 | 12,883 | 12,521 | 12,058 | 11,505 |

The historical, and projected data from MAPC, UMDI and Stantec are presented in Figure 3. Both the MAPC and UMDI population projection models predict a decrease in population for the Town of Holliston. Stantec first developed projections based on the historical data, and then developed projections based on the trends observed with the MAPC and UMDI data. Considering that historical population for the Town indicated a gradual increase in population while the MAPC and UMDI indicated a decrease for future years, Stantec developed two other sets of projections based on combinations of the respective trend lines associated with the historical,

MAPC and UMDI data to show what the actual growth pattern for future trends might look like.

**Figure 3**  
**Historical and Projected Population Trends**



The different projection scenarios developed were reviewed with the Holliston Town Planner. Based on discussions, it was determined that the Stantec projection that considers only Historical and MAPC data best represents the Town's future population trend. Table 10 shows the population projections that serve as the basis for future water use consumption in this report.

**Table 10**  
**Stantec Population Projections**

| <u>Year</u> | <u>Estimated Population</u> | <u>Percentage Change</u> |
|-------------|-----------------------------|--------------------------|
| 2025        | 15,062                      | -                        |
| 2030        | 15,128                      | 0.44%                    |
| 2035        | 15,195                      | 0.44%                    |
| 2040        | 15,261                      | 0.44%                    |

## FUTURE WATER DEMAND

One of the objectives of this plan is to estimate future water demands, and use these estimates to determine the resiliency of the current water system supply. If inadequacies are found, a plan for system improvements will be developed.

Estimated future demands include residential, commercial, industrial, agricultural, municipal/institutional/non-profits, confidently estimated municipal use, and unaccounted-for water usage. Residential demand is dependent on changes in population. Commercial/ industrial demand depends on changes in economic development. As population and commercial/ industrial activities increase, the amount of water needed increases. By estimating the future residential demand and commercial demand and knowing the percentage of total demand represented by the unaccounted-for water, the future total demand can be calculated.

Projected water use is essential in determining the future adequacy of the supply system. The following method was used for determining future residential water demands:

1. Consumption records from 2009 through 2020 supplied by the Holliston Water Department were analyzed (see Table 3).
2. Historical residential demands were divided by the population to determine historical per capita residential demand (see Table 6).
3. Future population projections were estimated (see Table 10).
4. Average historical per capita residential demand was multiplied by the projected population for future years to calculate average domestic water demands for future planning years.

### Average Daily Demand

The Average Day Demand (ADD) in 2020 was 0.929 MGD. To project future water demands, the residential water use was estimated based on historical residential gallons per capita per day multiplied by the population projections developed for 2025, 2030, 2035 and 2040 (see Table 10). The average daily demand for all other water consumption categories for the planning period was estimated based on the relationship with the residential water use for the different years, and considering the overall percentage uses for the period of 2009 through 2020. Stantec assumed that UAW will continue to remain below the UAW requirement of 10% through 2040. The projected average day demands are presented as a percent of total daily demand in Table 11, and the corresponding daily demand volumes are presented in Table 12 and Table 13.

**Table 11**  
**Projected Percentage Average Day Demand by Use Category**

| Year | Residential | Commercial/<br>Business | Agricultural | Industrial | Municipal/Institutional/<br>Non-profits | Other | Total<br>CEMU | UAW*  | Total |
|------|-------------|-------------------------|--------------|------------|---|-------|---------------|-------|-------|
| 2025 | 70.1%       | 5.93%                   | 0.61%        | –          | 1.93%                                   | 1.15% | 10.3%         | 10.0% | 100%  |
| 2030 | 70.1%       | 5.93%                   | 0.61%        | –          | 1.93%                                   | 1.15% | 10.3%         | 10.0% | 100%  |
| 2035 | 70.1%       | 5.93%                   | 0.61%        | –          | 1.93%                                   | 1.15% | 10.3%         | 10.0% | 100%  |
| 2040 | 70.1%       | 5.93%                   | 0.61%        | –          | 1.93%                                   | 1.15% | 10.3%         | 10.0% | 100%  |
| AVG  | 70.1%       | 5.93%                   | 0.61%        | –          | 1.93%                                   | 1.15% | 10.3%         | 10.0% | 100%  |

\* Assumed UAW for period 2025 through 2040 remains at 10% (similar to 2019 and 2020)

**Table 12**  
**Projected Average Day Demand (MGY) by Use Category**

| Year | Residential | Commercial/<br>Business | Agricultural | Industrial | Municipal/Institutional/<br>Non-profits | Other | Total<br>CEMU | UAW* | Total |
|------|-------------|-------------------------|--------------|------------|---|-------|---------------|------|-------|
| 2025 | 255.6       | 21.6                    | 2.21         | –          | 7.04                                    | 4.18  | 37.6          | 36.5 | 364.7 |
| 2030 | 256.7       | 21.7                    | 2.22         | –          | 7.07                                    | 4.20  | 37.8          | 36.6 | 366.3 |
| 2035 | 257.8       | 21.8                    | 2.23         | –          | 7.10                                    | 4.22  | 38.0          | 36.8 | 368.0 |
| 2040 | 259.6       | 22.0                    | 2.25         | –          | 7.15                                    | 4.25  | 38.2          | 37.1 | 370.6 |
| AVG  | 257.4       | 21.8                    | 2.23         | –          | 7.09                                    | 4.21  | 37.9          | 36.7 | 367.4 |

**Table 13**  
**Projected Average Day Demand (MGD) by Use Category**

| Year | Residential | Commercial/<br>Business | Agricultural | Industrial | Municipal/Institutional/<br>Non-profits | Other  | Total<br>CEMU | UAW*  | Total |
|------|-------------|-------------------------|--------------|------------|---|--------|---------------|-------|-------|
| 2025 | 0.700       | 0.059                   | 0.0061       | –          | 0.0193                                  | 0.0115 | 0.103         | 0.100 | 0.999 |
| 2030 | 0.703       | 0.060                   | 0.0061       | –          | 0.0194                                  | 0.0115 | 0.104         | 0.100 | 1.004 |
| 2035 | 0.706       | 0.060                   | 0.0061       | –          | 0.0195                                  | 0.0116 | 0.104         | 0.101 | 1.008 |
| 2040 | 0.709       | 0.060                   | 0.0061       | –          | 0.0195                                  | 0.0116 | 0.104         | 0.101 | 1.012 |
| AVG  | 0.705       | 0.060                   | 0.0061       | –          | 0.0194                                  | 0.0115 | 0.104         | 0.101 | 1.006 |

The projected average day demands consider all the use categories that were in play for the period 2009 through 2020, except for the use category "Industrial" since it has remained at 0 MGD during that timeframe. Water demand for the different user categories, including UAW, are projected to remain consistent in terms of overall percentage of water use over the planning period. Total water demand during the period of 2025 through 2040 is projected to be comparable to the demands that have been experienced during the period of 2009 through 2020 with a moderate increase over more recent years. UAW has been exceptionally low in recent years and for planning purposes, UAW has been projected to remain at 10% over the planning period. This results in an overall increase in water use in the near term as compared to 2020 data, with an overall decreasing trend in projected total water demand over the planning period due to decreasing population.



## Maximum Daily Demand

The projected maximum day demands from 2025 through 2040 are presented in Table 14. These were calculated by multiplying the projected average day demand for those years with the average of the maximum day to average day ratio from the historical period of 2009 through 2020. An average day demand of 0.989 MGD was calculated for 2025, and a maximum daily demand ratio of 1.68 was selected for the 20-year planning period.

**Table 14**  
**Projected Maximum and Average Day Demands**

| <u>Year</u>                     | <u>2025</u> | <u>2030</u> | <u>2035</u> | <u>2040</u> |
|---------------------------------|-------------|-------------|-------------|-------------|
| Average Day                     | 0.989       | 0.999       | 1.004       | 1.008       |
| Maximum Day (1.68*×Average Day) | 1.657       | 1.674       | 1.682       | 1.689       |

\*1.68 is the average of the maximum day to average day ratio from the period of 2009 through 2020.





**4**  
**HYDROGEOLOGICAL  
INVESTIGATIONS  
REVIEW**



# 4. HYDROGEOLOGICAL INVESTIGATIONS REVIEW

In November 1997, a pumping test was conducted for Well #7 as a potential Public Water Supply source). This well source was approved in a Permit from the MADEP in 2001. Since that time, Well 8 was also constructed as a replacement well to Well 2.

In 2002, an investigation of potential locations for a new well source was conducted. The investigation led to a potential location on the southeast end of Chestnut Street, and another potential location in a valley encompassed by Hanlon Road, Marshall Street and Wilson Street. However, further investigations indicated that either locations would not be a suitable site for the new well source since the overburden and aquifers were found to be too thin for the installation of a gravel-packed well, and may contribute to low yield, and surface water infiltration and runoff into the well.

In more recent years there has not been any investigations into new source development. The following section will evaluate the need for future well source investigation.

The background is a dark gray gradient with several large, semi-transparent bubbles of varying sizes on the right side. A large, white, stylized number '5' is positioned on the left side, partially overlapping the bubbles. The text 'WELL DATA' is written in a bold, orange, sans-serif font across the middle of the page, with the '5' overlapping the 'W' and 'E'.

# 5 WELL DATA

# 5. WELL DATA

## PUMPING RATES


Table 15 shows the MassDEP approved pumping rate, year when the well meter was installed, year when the well meter was last calibrated, and the operational status for each groundwater source as listed in Town’s ASRs. Well 2136000-03G was replaced with well 2136000-04G, and Well 03G is considered an emergency source of supply although there is no mechanical equipment in-place to allow pumping water from it. In 2012, Well 2136000-08G was connected to the water distribution system as a replacement to well 2136000-02G. In 2014, well 2136000-07G was connected to the water distribution system.

**Table 15**  
**Approved Daily Pumping Rate (MGD) for each Well**

| <u>Well ID</u> | <u>Name</u>          | <u>Approved Daily Pumping Rate (MGD)</u> | <u>Well Meter Installation Year</u> | <u>Last Meter Calibration Year</u> | <u>Operational Status</u> |
|----------------|----------------------|--|-------------------------------------|------------------------------------|---------------------------|
| 2136000-01G    | Norfolk Street #1    | 0.307                                    | 1960                                | 2005                               | Offline                   |
| 2136000-02G    | Maple Street #2      | 0.297                                    | unknown                             | unknown                            | Offline                   |
| 2136000-03G    | Washington Street #3 | 0.196                                    | 1950                                | 1950                               | Offline                   |
| 2136000-04G    | Washington Street #4 | 0.465                                    | 2007                                | 2019                               | Online                    |
| 2136000-05G    | Central Street #5    | 0.684                                    | 2007                                | 2019                               | Online                    |
| 2136000-06G    | Brook Street #6      | 0.864                                    | 1997                                | 2019                               | Online                    |
| 2136000-07G    | Mohawk Path Well #7  | 0.860                                    | 2000                                | 2019                               | Online                    |
| 2136000-08G    | Maple Street #8      | 0.297                                    | 2000                                | 2019                               | Online                    |

Figure 4 shows the average production rate for each well for the years 2010 through 2020 with respect to the corresponding approved daily pumping rate (MGD). Data for the years 2009, 2011, and 2013 were not available. Water supply from wells 2136000-01G and 2136000-02G ended in 2012. There was no water production from Well 2136000-03G during the timeframe investigated. The highest pumping rate occurred at wells 2136000-06G and 2136000-07G. The authorized withdrawal for these two sources is measured by the total pump rate at both sources. The next highest pumping was wells 2136000-05G, and 2136000-08G. Only wells 2136000-05G and 2136000-08G appear to be operating close to their respective approved daily pumping rate.

**Figure 4**  
**Average Well Production Rate (MGD) per Year**




— Depicts approved daily pumping rate (MGD) for well

Table 16 through Table 22 together with corresponding Figure 5 through Figure 11 show the volume pumped from each well the years 2010 through 2020. Data for the years 2009, 2011, and 2013 were not available. The amount of water pumped from wells 2136000-05G and 2136000-06G followed an overall increasing trend, while the amount of water pumped from wells 2136000-04G, 2136000-07G, and 2136000-08G followed an overall decreasing trend. There was no water production from wells 2136000-01G and 2136000-02G after 2012.

**Table 16**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-01G**

| Period    | 2010 | 2012 | 2014 | 2015 | 2016 | 2017 | 2018 | 2019 | 2020 |
|-----------|------|------|------|------|------|------|------|------|------|
| January   | 2.26 | 2.54 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| February  | 2.29 | 2.44 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| March     | 3.24 | 2.48 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| April     | 4.04 | 3.97 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| May       | 4.38 | 3.70 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| June      | 4.10 | 3.79 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| July      | 5.35 | 4.71 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| August    | 6.03 | 2.75 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| September | 3.26 | 2.62 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| October   | 3.74 | 0.38 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| November  | 3.98 | 0.02 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| December  | 4.22 | 0.04 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| AVERAGE   | 3.91 | 2.45 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |

**Figure 5**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-01G**




..... Depicts trendline based on annual average volume of water pumped from well.

**Table 17**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-02G**

| Period    | 2010 | 2012 | 2014 | 2015 | 2016 | 2017 | 2018 | 2019 | 2020 |
|-----------|------|------|------|------|------|------|------|------|------|
| January   | 2.56 | 2.39 | 0.00 | 0.00 | 0.00 | 0.00 | -    | -    | -    |
| February  | 2.30 | 2.31 | 0.00 | 0.00 | 0.00 | 0.00 | -    | -    | -    |
| March     | 0.59 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | -    | -    | -    |
| April     | 3.59 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | -    | -    | -    |
| May       | 5.01 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | -    | -    | -    |
| June      | 4.06 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | -    | -    | -    |
| July      | 5.62 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | -    | -    | -    |
| August    | 6.18 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | -    | -    | -    |
| September | 3.82 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | -    | -    | -    |
| October   | 4.35 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | -    | -    | -    |
| November  | 4.56 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | -    | -    | -    |
| December  | 4.53 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | -    | -    | -    |
| AVERAGE   | 3.93 | 0.39 | 0.00 | 0.00 | 0.00 | 0.00 | -    | -    | -    |

"-" means well not included in the ASR of that year.

**Figure 6**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-02G**




..... Depicts trendline based on annual average volume of water pumped from well.



**Table 18**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-04G**

| Period    | 2010 | 2012 | 2014 | 2015 | 2016 | 2017 | 2018 | 2019 | 2020 |
|-----------|------|------|------|------|------|------|------|------|------|
| January   | 0.00 | 0.00 | 1.10 | 0.66 | 1.14 | 2.09 | 1.63 | 2.88 | 1.75 |
| February  | 0.00 | 0.00 | 0.34 | 0.73 | 0.93 | 1.48 | 1.75 | 2.18 | 1.53 |
| March     | 0.00 | 0.00 | 1.13 | 0.70 | 1.29 | 2.59 | 2.33 | 2.37 | 1.43 |
| April     | 0.00 | 0.00 | 1.14 | 0.92 | 1.31 | 1.98 | 2.57 | 3.19 | 1.36 |
| May       | 0.00 | 0.00 | 4.46 | 1.24 | 2.84 | 2.68 | 3.13 | 2.89 | 2.63 |
| June      | 0.00 | 0.00 | 1.23 | 1.28 | 2.81 | 3.25 | 3.10 | 2.31 | 2.98 |
| July      | 0.00 | 0.00 | 0.59 | 1.42 | 3.50 | 2.39 | 3.41 | 3.15 | 3.27 |
| August    | 0.00 | 0.00 | 1.20 | 1.49 | 2.59 | 2.49 | 3.08 | 2.62 | 2.89 |
| September | 0.00 | 0.00 | 0.97 | 2.27 | 2.97 | 2.48 | 2.47 | 2.22 | 2.93 |
| October   | 0.00 | 0.00 | 0.72 | 1.31 | 2.03 | 2.85 | 2.55 | 1.81 | 2.74 |
| November  | 0.00 | 0.00 | 0.25 | 0.83 | 1.63 | 1.87 | 1.54 | 1.25 | 2.03 |
| December  | 0.00 | 0.00 | 0.34 | 1.29 | 2.39 | 1.60 | 1.68 | 1.18 | 3.41 |
| AVERAGE   | 0.00 | 0.00 | 1.12 | 1.18 | 2.12 | 2.31 | 2.44 | 2.34 | 2.41 |

**Figure 7**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-04G**




..... Depicts trendline based on annual average volume of water pumped from well.

**Table 19**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-05G**

| Period    | 2010  | 2012  | 2014  | 2015  | 2016  | 2017  | 2018  | 2019  | 2020  |
|-----------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| January   | 16.11 | 18.36 | 18.27 | 14.72 | 10.45 | 8.20  | 14.21 | 8.06  | 11.22 |
| February  | 14.39 | 15.00 | 16.33 | 12.99 | 11.09 | 7.65  | 11.03 | 7.26  | 10.45 |
| March     | 16.31 | 15.17 | 17.85 | 19.28 | 10.34 | 9.71  | 9.75  | 9.85  | 9.43  |
| April     | 14.30 | 16.14 | 17.16 | 17.75 | 10.07 | 12.06 | 8.58  | 9.59  | 9.34  |
| May       | 16.91 | 17.49 | 8.65  | 18.97 | 13.32 | 15.02 | 9.20  | 9.44  | 10.21 |
| June      | 16.27 | 15.09 | 19.08 | 17.98 | 15.65 | 14.27 | 10.92 | 9.37  | 9.47  |
| July      | 14.91 | 17.59 | 18.75 | 17.89 | 17.45 | 14.64 | 10.23 | 9.20  | 11.31 |
| August    | 3.59  | 17.70 | 19.08 | 17.77 | 15.46 | 14.51 | 9.42  | 13.27 | 13.05 |
| September | 17.59 | 15.70 | 16.21 | 16.45 | 13.44 | 13.59 | 8.85  | 13.61 | 12.63 |
| October   | 16.97 | 17.34 | 17.30 | 16.80 | 13.45 | 14.52 | 9.39  | 13.37 | 12.57 |
| November  | 17.28 | 16.64 | 16.14 | 12.91 | 13.32 | 13.54 | 9.21  | 11.37 | 12.39 |
| December  | 18.14 | 17.80 | 17.12 | 10.03 | 2.22  | 14.94 | 9.47  | 11.04 | 0.06  |
| AVERAGE   | 15.23 | 16.67 | 16.83 | 16.13 | 12.19 | 12.72 | 10.02 | 10.45 | 10.18 |

**Figure 8**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-05G**




..... Depicts trendline based on annual average volume of water pumped from well.

**Table 20**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-06G**

| Period    | 2010  | 2012 | 2014 | 2015 | 2016 | 2017 | 2018 | 2019 | 2020 |
|-----------|-------|------|------|------|------|------|------|------|------|
| January   | 8.51  | 3.60 | 0.00 | 0.00 | 0.10 | 3.74 | 2.94 | 3.90 | 2.61 |
| February  | 6.89  | 4.38 | 0.00 | 0.00 | 0.00 | 2.96 | 2.78 | 3.31 | 3.17 |
| March     | 8.93  | 3.45 | 0.32 | 0.00 | 0.13 | 3.94 | 3.90 | 2.89 | 1.53 |
| April     | 5.75  | 2.82 | 0.84 | 0.00 | 0.16 | 3.20 | 3.68 | 4.62 | 1.72 |
| May       | 8.93  | 4.55 | 0.00 | 0.00 | 0.17 | 4.30 | 5.41 | 3.95 | 3.93 |
| June      | 12.82 | 6.83 | 0.00 | 0.00 | 0.18 | 5.80 | 5.82 | 4.56 | 5.91 |
| July      | 16.25 | 4.30 | 0.00 | 0.00 | 0.26 | 5.84 | 6.60 | 6.25 | 4.04 |
| August    | 14.20 | 3.84 | 0.00 | 0.00 | 0.21 | 5.31 | 5.55 | 3.22 | 3.13 |
| September | 9.83  | 3.39 | 0.00 | 0.00 | 0.12 | 4.76 | 4.97 | 2.23 | 2.95 |
| October   | 3.59  | 2.50 | 0.00 | 0.00 | 0.94 | 4.11 | 5.07 | 3.63 | 3.39 |
| November  | 0.00  | 2.35 | 0.00 | 0.00 | 3.28 | 2.80 | 3.73 | 0.00 | 2.90 |
| December  | 0.00  | 2.05 | 0.00 | 0.04 | 6.45 | 2.60 | 3.60 | 1.37 | 6.18 |
| AVERAGE   | 7.98  | 3.67 | 0.10 | 0.00 | 1.00 | 4.11 | 4.50 | 3.33 | 3.45 |

**Figure 9**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-06G**




..... Depicts trendline based on annual average volume of water pumped from well.

**Table 21**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-07G**

| Period    | 2010 | 2012 | 2014  | 2015 | 2016  | 2017 | 2018  | 2019 | 2020  |
|-----------|------|------|-------|------|-------|------|-------|------|-------|
| January   | -    | -    | 7.84  | 2.46 | 5.38  | 5.40 | 6.00  | 7.06 | 5.39  |
| February  | -    | -    | 7.04  | 1.82 | 3.64  | 4.25 | 5.47  | 5.95 | 6.31  |
| March     | -    | -    | 7.43  | 1.86 | 5.33  | 5.52 | 7.50  | 5.22 | 3.38  |
| April     | -    | -    | 8.45  | 3.11 | 5.58  | 4.53 | 7.15  | 8.29 | 3.55  |
| May       | -    | -    | 18.22 | 8.50 | 11.46 | 5.99 | 10.12 | 7.17 | 7.75  |
| June      | -    | -    | 5.72  | 6.03 | 14.12 | 8.14 | 11.66 | 8.01 | 11.80 |
| July      | -    | -    | 6.06  | 6.40 | 11.65 | 8.11 | 12.53 | 9.93 | 8.16  |
| August    | -    | -    | 2.58  | 7.79 | 10.69 | 7.44 | 10.96 | 6.48 | 6.47  |
| September | -    | -    | 8.11  | 9.31 | 10.93 | 6.52 | 9.03  | 5.07 | 5.80  |
| October   | -    | -    | 6.03  | 6.63 | 10.47 | 7.10 | 9.15  | 2.60 | 6.49  |
| November  | -    | -    | 2.19  | 4.79 | 5.45  | 5.59 | 6.87  | 5.00 | 5.94  |
| December  | -    | -    | 1.06  | 5.80 | 9.63  | 4.94 | 6.48  | 4.24 | 12.07 |
| AVERAGE   | -    | -    | 6.73  | 5.38 | 8.69  | 6.13 | 8.58  | 6.25 | 6.92  |

"-" means well not included in the ASR of that year.

**Figure 10**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-07G**




..... Depicts trendline based on annual average volume of water pumped from well.

**Table 22**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-08G**

| Period    | 2010 | 2012 | 2014 | 2015 | 2016 | 2017 | 2018 | 2019 | 2020 |
|-----------|------|------|------|------|------|------|------|------|------|
| January   | -    | 0.00 | 9.13 | 7.59 | 7.59 | 9.09 | 7.89 | 8.85 | 5.13 |
| February  | -    | 0.00 | 8.20 | 6.20 | 6.20 | 8.04 | 7.85 | 7.94 | 2.90 |
| March     | -    | 3.61 | 8.79 | 4.32 | 4.32 | 8.72 | 8.15 | 8.69 | 9.18 |
| April     | -    | 4.06 | 9.15 | 4.59 | 4.59 | 8.55 | 8.48 | 8.43 | 8.94 |
| May       | -    | 3.96 | 9.45 | 8.22 | 8.22 | 8.84 | 8.77 | 8.79 | 9.26 |
| June      | -    | 5.70 | 8.83 | 7.62 | 7.62 | 8.56 | 8.45 | 8.52 | 8.89 |
| July      | -    | 7.17 | 8.91 | 8.07 | 8.07 | 8.75 | 8.50 | 8.71 | 8.86 |
| August    | -    | 6.64 | 8.66 | 7.02 | 7.02 | 8.60 | 8.67 | 8.53 | 7.13 |
| September | -    | 6.25 | 6.94 | 5.46 | 5.46 | 8.28 | 8.48 | 8.27 | 5.76 |
| October   | -    | 6.24 | 6.90 | 5.57 | 5.57 | 8.02 | 8.85 | 8.20 | 3.97 |
| November  | -    | 6.56 | 6.91 | 6.26 | 6.26 | 7.08 | 8.64 | 8.13 | 4.63 |
| December  | -    | 5.82 | 1.06 | 8.62 | 8.62 | 7.62 | 8.88 | 8.44 | 8.33 |
| AVERAGE   | -    | 4.67 | 7.74 | 6.63 | 6.63 | 8.34 | 8.47 | 8.46 | 6.91 |

"-" means well not included in the ASR of that year.

**Figure 11**  
**Monthly Volume (MG) of Water Pumped from Well 2136000-08G**



..... Depicts trendline based on annual average volume of water pumped from well.

## WMA PERMITS AND REGISTRATIONS

The Town of Holliston’s Water Management Act (WMA) Registration and related permit allows for the daily average withdrawal of 1.14 MGD (i.e. annual average of 416.1 MGY) from the Charles River basin at the rates shown in Table 23. The total volume of 1.41 MGD allocated for Period Four is the maximum interim volume that may be allocated to the Town, and is reserved pending the completion of a water needs forecast by the Massachusetts Department of Conservation and Recreation for the Town.

**Table 23**  
**Maximum Authorized Raw Water Withdrawal Volumes per WMA**

| Five-Year Periods           |                       | Permit              |                      | Permit + Registration |                      |
|-----------------------------|-----------------------|---------------------|----------------------|-----------------------|----------------------|
|                             |                       | Daily Average [MGD] | Annual Average [MGY] | Daily Average [MGD]   | Annual Average [MGY] |
| Period One; Years 1 – 5     | 3/1/2010 to 2/28/2014 | 0                   | 0                    | 1.14                  | 416.10               |
| Period Two; Years 6 – 10    | 3/1/2014 to 2/29/2019 | 0                   | 0                    | 1.14                  | 416.10               |
| Period Three; Years 11 – 15 | 3/1/2019 to 2/28/2024 | 0                   | 0                    | 1.14                  | 416.10               |
| Period Four; Years 16 – 20  | 3/1/2024 to 2/28/2029 | 0.27                | 98.55                | 1.41                  | 514.65               |

The volume allocated for Period One through Period Three includes withdrawal from the following registered withdrawal points:

| Identification Code | Type        | Name                 |
|---------------------|-------------|----------------------|
| 2136000-01G         | Groundwater | Norfolk Street #1    |
| 2136000-02G         | Groundwater | Maple Street #2      |
| 2136000-04G         | Groundwater | Washington Street #4 |
| 2136000-05G         | Groundwater | Central Street #5    |
| 2136000-06G         | Groundwater | Brook Street #6      |

The volume allocated for Period 4 includes an additional 0.27 MGD for Well #7 as an authorized withdrawal point:


| Identification Code | Type        | Name    |
|---------------------|-------------|---------|
| 2136000-07G         | Groundwater | Well #7 |

Note that the approved daily pumping rate for Well #7 and Well #6 is limited to a maximum combined daily pumping rate of 0.86 MGD, which represents the previously approved pumping rate for Well #6. The limitation to this volume is due to the potential impact of withdrawals on nearby wetlands and

Dopping Brook. MassDEP will reevaluate this volume in the future after several years of monitoring.

The Town of Holliston's original WMA permit expired on February 28, 2009; however, an interim permit was issued authorizing the continued withdrawal of the previously permitted volumes for the Wells #1, 2, 4, 5, and 6. In May 2002, the Town was issued another WMA permit for the inclusion of Well #7 as an approved source with an additional permitted volume allocated solely for it.

The Permit Extension Act has extended all Water Management Registrations by four (4) years; thereby rendering the Town's current Water Management Registrations to be effective through December 31, 2021. However, per Stantec communication with MassDEP, it is possible that another extension may be granted due to the ongoing COVID-19 pandemic. MassDEP will send to suppliers the necessary forms file a renewal request for WMA Registration in advance the renewal period.



**6**  
**WATER SUPPLY  
RECOMMENDATIONS**



# 6. WATER SUPPLY RECOMMENDATIONS

## HYDROGEOLOGICAL INVESTIGATION OF NEW SOURCE(S)

Based on the current review, the Town of Holliston's existing groundwater sources remain adequate to meet anticipated future demand. Hydrogeological investigation of new sources is at present not required.

It is recommended that the Town of Holliston continue being proactive with respect to its water system operational and maintenance practices especially during offseason, staffing of its well stations, and system resiliency during emergency situations. It is also recommended that the water quality at each well continue to be closely monitored especially in regard to emerging contaminants such as PFAS.

## OPERATIONAL AND MAINTENANCE PRACTICES FOR EXISTING SOURCES

The following sections describe the recommended operational and maintenance practices for the existing well pumping stations on a daily, weekly, monthly, and yearly basis.

### Daily or Weekly

- Check well pumping station interior and grounds for general cleanliness and condition, and for any threats to water quality.
- Check any warning lights or alarms – low water level in the well, intrusion, power outage, pump failure, etc.
- Read source water meter. Record water-production data in well house log.
- Read pump run hour meters and record data in well house log (unless automatic data storage is available).
- Check pump-cycling rate. If it runs continuously or cycles more than 6 times per hour, see pump troubleshooting.
- Check that instruments are properly calibrated.
- Check that generator is functional and on standby for a sudden power loss.

- Check well house buildings for signs of security problems – graffiti, vandalism, doors or locks damaged, entry, etc.
- Check wells source site after any adverse weather – high winds, heavy snow, ice, rains, etc.
- Check well water level if source capacity is marginal or there are drought conditions.

## Monthly

- Check area for excessive vegetation or dangerous conditions – uncut grass, brush, dead trees, fire hazard, etc.
- Check well pumping station control valves for proper positions, open or closed. This information should be posted.
- Check source control system – pressure switch settings, cycling, storage tank water levels, etc.
- Check well pumping station control valves for damage or leaks.
- Check for leaks – read source meter when you expect the water usage to be zero.
- Check well pump cycling and pressure switch settings, on/off pressures, and line pressures.

## Annually or Seasonally

- Check well site for water ponding, poor drainage areas, excessive vegetation, unhealthy trees, fire hazards, etc.
- Check well pumping stations conditions – corrosion, vent screens, vehicular or other damage, animal activity, etc.
- Check cold weather protection – insulation, heating system, alarm system, etc.
- Verify sanitary integrity of the sources – screened vents, no unprotected openings, electrical box sealed, etc.
- Evaluate source use designations (permanent, seasonal, emergency, or inactive).
- Exercise valves and test run emergency source wells to waste. Do not supply distribution system without water quality tests.
- Evaluate Emergency Response Plan and update as required.
- Review source related customer complaints and evaluate corrective actions and planning.
- Implement seasonal start-up or shut-down procedures.
- Review source water quality test results for trends, such as increasing iron and manganese.

## Less Than Once a Year

- Measure source pump capacity in gallons per minute (GPM) to detect pump output problems (pump test to confirm pump curve).
- Evaluate general source capacity to meet water system demand with water use and production records.
- Evaluate capacity of source water to provide water of a reliable quantity and quality acceptable to customers.
- Consider television inspection of the well interior and the well screens.



# 7 WATER MAIN IMPROVEMENTS PLANNING


# 7. WATER MAIN IMPROVEMENTS PLANNING

## GENERAL ASSET MANAGEMENT CONCEPTS

The development of an asset management system is a logical approach town officials use to allocate cost effective budgets. The theory of asset management is based on accurately predicting accelerated deterioration of assets. Figure 12 dramatically illustrates the key concept of making timely maintenance repairs, thereby averting the need for far more expensive structural repairs. The goal is to save money in both the short and long run by developing a program that minimizes expenditures.

The Town of Holliston initiated an asset management approach to the water distribution system assets in 2010. This report serves as an update to the previous report.

**Figure 12**  
**Typical Asset Management Deterioration Curve**



The curve shows the rate at which a typical asset deteriorates over time (Figure 12). An asset deteriorates slowly through the first two-thirds of its projected life span (the portion of the graph where the curve is nearly horizontal). This level of deterioration per year increases drastically (the portion where the curve becomes nearly vertical) as the asset continues through the last third of its life span. When the asset is near the end of its projected life span, the asset levels out at a slower rate in the bottom through the worst conditions

until it reaches failure (the curve returns to near horizontal). The point where a typical asset passes middle age, before the curve drops off sharply, is considered the critical zone in the asset's life. Before this point, it is relatively inexpensive to keep an asset in good service, while after this point, it becomes much more expensive to keep the asset in good service condition.

The asset management system formalizes the asset deterioration curve process by using computer software. The procedure is to collect, organize, and maintain a complete water system database that describes a particular water system network. This data is then analyzed to identify existing deterioration levels, prioritize cost-effective repairs, and create an optimal long-term spending plan. Asset Management provides the Town with a tool to make the best use of every available dollar.

## Study Approach

In 2010 Stantec completed an Asset Management Plan for the water distribution system assets. Since the development of that report the Town has been implementing an annual pipeline replacement program. This evaluation serves as an update to the previous study.

In 2010 the water system GIS data was developed using a combination of existing mapping and field data collection. Stantec conducted a Town-wide hydrant and valve inventory and assessment. Hydrants and valves were visually inspected, and the overall condition was documented in the GPS unit along with its coordinates. In addition to visual inspection, the model and manufacturing date (year) of each hydrant was also collected. All hydrant-manufactured years were then analyzed in GIS to determine the install date for a pipeline. On a single street if the majority of the hydrants were manufactured within 5 years of each other, then the earliest year was assigned as the "year installed" for the pipeline. When hydrants on a street were from a variety of years, the hydrant years were compared to the Town's existing listing of pipeline installation years and a decision was made based on the nearby pipeline age and available information.

This existing GIS data was updated to reflect the water system improvements that have been constructed over the last 10 years. Data was also collected from the Town on history of breaks, leaks, and water quality complaints. Stantec also collaborated with the Town on identifying problem areas within the water distribution system which may not be reflected in the break and water quality complaint data. Previous hydraulic studies were also reviewed to identify any pipe improvements that were recommended for hydraulic improvements.



**WATER MAIN  
IMPROVEMENTS  
METHODOLOGY**



# 8. WATER MAIN IMPROVEMENTS METHODOLOGY

## ASSET MANAGEMENT SOFTWARE

Today's computer management technology allows consolidation of multiple data for easy and efficient building, editing, sorting, and reporting. Stantec used CarteGraph Systems, Inc. - WATERview® software for storing and analyzing Holliston's water distribution system data. The database was custom tailored to reflect Holliston's specific decision-making criteria for selecting water main repair types for available and proposed budgets.

For analyzing Holliston's water distribution system, the Pipe Condition Index (PCI) served as the primary factor in determining the water main serviceability and performance. PCI is based on pipe material, age, and the pipes' proximity to potentially elevated ground water levels and is used to quantify the overall water main condition.

Within the Holliston water distribution system there are five (5) different pipeline materials: Asbestos Cement, Cast Iron, Ductile Iron, Steel and Poly Vinyl Chloride. Regardless of material, a pipeline's proximity to high groundwater can influence the deterioration rate of the pipeline. Water main performance curves were developed for each water main material type and whether the pipe was installed in a location where high groundwater may be present. The location of high groundwater levels was assumed based on proximity to wetlands and surface water.

### Pipe Condition Index (PCI)

Stantec generated a PCI for each inventoried water main in Holliston using pipe age and material data. Typically break history would also be included in generating a PCI but Holliston does not have a significant history of water main breaks. Most leaks in the system are not cause by breaks but by leaks at the service connections. Instead, the available break history provided was used as part to determine a Network Priority Rating (NPR). PCI is measured on a one hundred to zero scale, with one hundred representing a water main in excellent condition and zero describing a water main in extremely poor condition, or other words has outlived its expected service life.

### Three Treatment Repair Bands

Stantec's water main management software decision matrix uses three broad category ranges to group the calculated PCI numbers into three major repair bands. An individual pipe segment will fall into a particular band based on

user-defined criteria such as material type, age, and ground water level conditions. Then each segment is assigned a repair alternative candidate with the prescribed treatment band. Table 24 presents the category ranges represented by the PCI bands.

**Table 24**  
**PCI Treatment Band Ranges**

| Action     | PCI Band # | PCI Range | Condition         | Notes   |
|------------|------------|-----------|-------------------|---|
| Do Nothing | 1          | 100 – 65  | Excellent to Good | Strong reliability  |
| Monitor    | 2          | 65 – 5    | Fair              | Acceptable condition/performance  |
| Replace    | 3          | 5 – 0     | Failure           | Outlived service life, likely in need of pipe replacement and/or inadequate fire flow protection/ criticality |

- When pipes are in near perfect condition, the **Do Nothing** category (Band #1) prescribes no work. Pipes are highly dependable and have an excellent performance track record.
- The **Monitor/Maintenance** category (Band #2) is categorized for pipes in reasonably good to fair condition. This treatment band has the widest PCI range, as these pipes have plenty of remaining service life, but are subject to “monitoring of health”. This treatment category would include leak detection, clean and lining cast iron pipe, inspecting external pipe conditions, pipe excavations, etc.
- The **Replace** category (Band #3) represents pipes that are near the end of their expected service life and warrants pipe replacement. Quite often, project level evaluation through test pit, field sampling, and cutting out a pipe section/coupon is done to evaluate pipe integrity prior to construction.

### Priority Ranking and Future Projection

After all water main segment repairs are assigned, the software prioritizes needed system repairs based on the highest projected Network Priority Ranking (NPR). The NPR value uses variables representing break history, fireflow protection adequacy, complaint history, and criticality. Although water main repairs could solely be prioritized on an “oldest-first” basis, Stantec and Holliston Water Department chose to maximize its available water funds by generating an NPR that favors repairs that have outlived its service life and critical components to the water distribution system.

First a backlog scenario was run to establish the current conditions of the infrastructure then a future plan was developed. Each plan year, the software prepares a future water main condition projection, exhausts the assigned budget, and then produces an annual list of water main segments to include in the repair program. The system also takes inflation into account for the time value of money. In these cases, a 3.5% inflation rate was used. Figure 13 shows the scenario analysis model. Having explained the methodology built into the



water system asset management software, the next section describes the existing water main system conditions in Holliston.

**Figure 13**  
**Pipe Segment Analysis**

### Segment Analysis Information

**Analysis Model**

Model ID:  New Model

Start Date:  Save Model

Scope:

Description:

Backlog = \$17,716,861

PCI = 46.96

Settings Calculate Plans Planned Results

### Summary

**Budget Summary Report**

This report shows the total cost of improvement, as well as the predicted Overall Condition Index (OCI) for each plan year in a scenario. The report is filtered by Model and grouped by Scenarios.

**Budget Surplus Report**

This report presents the original budget, as well as the used amount and the surplus, for each plan year in a scenario.

**Recommendations Report**

This report describes the annual recommended activities, total cost of improvement and improved/predicted condition Overall Condition Index (OCI) for all the segments in a particular scenario. The report is filtered to a Model ID and Scenario, and is grouped by Plan Year.

Record: 1 of 1 ⏪ ⏩ ⏴ ⏵

**Scenarios**

Scenario:  Protocol:

Description:  Time Frame:

Do Best First:  Is OCI Driven:


Done By:  Budget:

Reviewed By:  Inflation:

Status:  Interest Rate:

**Network OCI Schedules:**

|   | Improved Network | Plan Year | Target Network |
|---|------------------|-----------|----------------|
| ▶ | 62.94            | 1         | 100            |



**WATER MAIN  
EXISTING  
CONDITIONS**


# 9. WATER MAIN EXISTING CONDITIONS

## WATER MAIN MATERIAL AND CURRENT PCI

The Town of Holliston water distribution includes approximately 90 miles of pipe. This water distribution system is predominantly asbestos cement pipe material. The system is comprised of 61.5 miles of asbestos cement, 16.7 miles of ductile iron, 9.5 miles of poly vinyl chloride, 1.0 mile of steel, and 0.1 mile of cast iron pipe.

Stantec determined that the Town's average water main system network PCI in the Fall of 2021 was 47. This PCI average value generally represents a water main in "fair" condition. Figure 14 illustrates today's mile distribution based on the repair treatment bands. Treatment bands are broken into Do Nothing & Monitor, Cement Line, Small Pipes (8 in. diameter and less) and Medium Pipes (10-12 in. diameter) for Major and Minor roadways.

**Figure 14**  
**Town-wide Pipe Distribution in Miles by Repair Activity**



## DISTRIBUTION OF PIPES BY AGE

Holliston has approximately 90 miles of piping that make up its water main distribution system. The categorization of water main pipe segments by age show that 21% (18.8 miles) of pipe was installed between the 1940s and 50s; 45% (30.2 miles) were installed between the 60s and 70s; 25% (22.5 miles) of pipes between the 80s and 90s, and 9% (8.3 miles) of pipe were installed after 2000 (Figure 15). Over one-half of the pipe distribution network is over 40 years old.

Appendix A contains the PCI values for each individual water main pipe segment.

**Figure 15**  
**Pipe Distribution in Miles by Year Installed**





Figure 16 shows a map illustrating town-wide pipe age.



**Legend**

**Date Installed**

- 1940s
- 1950s
- 1960s
- 1980s
- 1990s
- 2000s
- 2010s



**Figure 16**  
**Map of Town-wide Pipe Age**

## CURRENT WATER MAIN BACKLOG

Backlog is defined as the cost of repairing all the water main which are already due for replacement within one year and bringing the average PCI of those water mains to a near perfect 100. Backlog is a “snapshot” or relative measure of outstanding repair work. The backlog not only represents how far behind the Holliston water system distribution network is in terms of its present physical condition, but its cost value serves as a benchmark to measure the impact of various funding scenarios. The current backlog offers a basis for comparison to future and/or past year's backlog(s). Backlog dollars represent the cost for design engineering, water main installation and pavement trench restoration only, it does not include related repair cost for other roadway/ pavement rehabilitation improvements. The backlog is based on a replacement ranging between \$200-\$350 per foot depending on size and roadway location. This variance in the construction cost per foot was assigned to account for the additional existing utilities and traffic management required for more major roadways.

As of Fall 2021, Holliston's backlog of water main repair work totaled \$17,716,861; an increase of over \$12 million in the last 11 years. This cost estimate consists \$41,301 in cement line work, \$7,130,501 in small pipe replacement on minor roadways, \$6,740,305 in small pipe replacement on major roadways, \$174,292 in medium pipe replacement on minor roadways and \$3,630,461 in medium pipe replacement on major roadways. See Figure 17.

**Figure 17**  
**Dollar Backlog of Outstanding Repairs**






Figure 18 shows a map illustrating town-wide backlog.



### Legend

#### Repair Type

- Do Nothing & Monitor
- Cement Line
- Small Pipe (Minor)
- Small Pipe (Major)
- Medium Pipe (Minor)
- Medium Pipe (Major)



**Figure 18**  
**Map of Town-wide Backlog**





# 10 MODEL/PLANNING PROCESS

# 10. MODEL/PLANNING PROCESS

## BUDGET ANALYSIS

The analysis software of the asset management system is where financial determinations and projections are made. Consideration is given to the required budget and need for replacement, based on the supplied information from meetings with the Town and Stantec.

The planning process determines the most beneficial improvement plan based on the dollars available for rehabilitation or replacement and other factors. Asset management pulls together these components in its Network Priority Ranking (NPR) value in order to develop a cost-effective program. As previously stated, the NPR was configured to maximize water main funds.

Appendix A contains a backlog report of the suggested segment repairs, the associated costs, PCI, and NPR - as detailed in the Methodology section, the NPR number reflects the comparative merit of repairing one water main section over another, fire flow deficiency break history, customer complaints, and criticality. This report has been ordered alphabetically. The balance of this section explains the results of Holliston's scenario projections, and concludes with a long-term action plan based on the scenario findings.

## SCENARIO FINDINGS

The following sections provide an overview of the budget/planning model results. Two budget/planning scenarios were modeled. These include: Zero Budget and Anticipated Budget Scenarios

After determining Holliston's existing backlog of work, Stantec projected the network average pipe condition index and backlog at a zero annual appropriation rate for water main replacement over the next 25-years; then anticipated appropriation rate for 25-years with a priority on repairing the highest priority pipes first.

All funding scenarios were calculated for a duration of 25-years. Focusing on higher priority projects, including the closing of loops and expansion of infrastructure the first 16 years, then prioritizing the highest ranked pipe segments.

All the scenarios accounted for the "optimum" NPR where NPR focuses on repairing the worst segments first. The dollar amounts appropriated incorporate a 3.50% annual inflation rate. **Therefore, where the annual water main program appropriation appears to remain the same, it in fact represents a net budget decrease due to the impact of inflation.**

In the scenario specific summary tables that follow, each plan begins with the same network average PCI, then shows the new network average PCI at the end of each plan period. The tables also use the same amount of outstanding repair work (backlog) at the start of each plan period, so the first plan year backlog will appear the same for each of the scenarios. The successive years document the impact of the funding plan on comparison of water main pipe network average conditions and backlog while accounting for a 3.5% inflation rate.

## Zero Budget

As a baseline, a worst-case scenario was developed to show how the backlog would increase over a 25-year period, if there was no funding for water main replacements. Table 25 shows the change in backlog with no funding.

**Table 25**  
**Zero Budget – Impact on Backlog**

| Year    | Funding | PCI Level | Backlog       |
|---------|---------|-----------|---------------|
| Present |         | 47.0      | \$17,716,861  |
| FY 2023 | \$0     | 45.5      | \$18,598,747  |
| FY 2024 | \$0     | 44.1      | \$19,249,329  |
| FY 2025 | \$0     | 42.8      | \$23,801,317  |
| FY 2026 | \$0     | 41.4      | \$24,633,840  |
| FY 2027 | \$0     | 40.1      | \$26,633,841  |
| FY 2028 | \$0     | 38.8      | \$28,531,578  |
| FY 2029 | \$0     | 37.6      | \$43,384,144  |
| FY 2030 | \$0     | 36.4      | \$47,575,021  |
| FY 2031 | \$0     | 35.3      | \$49,244,341  |
| FY 2032 | \$0     | 34.4      | \$54,661,225  |
| FY 2033 | \$0     | 33.5      | \$61,381,337  |
| FY 2034 | \$0     | 32.6      | \$67,925,882  |
| FY 2035 | \$0     | 31.9      | \$74,248,804  |
| FY 2036 | \$0     | 31.1      | \$80,810,641  |
| FY 2037 | \$0     | 30.4      | \$84,501,430  |
| FY 2038 | \$0     | 29.8      | \$87,796,829  |
| FY 2039 | \$0     | 29.2      | \$98,716,363  |
| FY 2040 | \$0     | 28.6      | \$103,415,915 |
| FY 2041 | \$0     | 28.1      | \$111,479,835 |
| FY 2042 | \$0     | 27.6      | \$118,302,818 |
| FY 2043 | \$0     | 27.1      | \$123,661,594 |
| FY 2044 | \$0     | 26.7      | \$128,977,117 |
| FY 2045 | \$0     | 26.3      | \$134,938,943 |
| FY 2046 | \$0     | 25.9      | \$141,009,813 |
| FY 2047 | \$0     | 25.5      | \$148,266,402 |

In a 25-year period, this scenario shows that with no water main replacement funding, the network average PCI dropped more than 20 points. Further, the numbers show the repair backlog increasing by eight times to \$148,000,000.

### Anticipated Budget

Based on discussions with the Town of Holliston, Stantec evaluated the 25-year projection on an Anticipated Budget scenario based on an \$1,300,000 funding level that the Town can secure to maintain and repair its water mains. Table 26 presents the results of this funding level.


**Table 26**  
**Anticipated Budget – Impact on Backlog**

| Year    | Funding     | PCI Level | Backlog      |
|---------|-------------|-----------|--------------|
| Present |             | 47.0      | \$17,716,861 |
| FY 2023 | \$1,300,000 | 48.2      | \$16,417,693 |
| FY 2024 | \$1,300,000 | 47.9      | \$15,954,015 |
| FY 2025 | \$1,300,000 | 47.7      | \$15,214,174 |
| FY 2026 | \$1,300,000 | 47.4      | \$18,340,450 |
| FY 2027 | \$1,300,000 | 46.9      | \$17,699,573 |
| FY 2028 | \$1,300,000 | 46.6      | \$17,625,001 |
| FY 2029 | \$1,300,000 | 46.2      | \$18,451,807 |
| FY 2030 | \$1,300,000 | 46.0      | \$31,582,353 |
| FY 2031 | \$1,300,000 | 45.8      | \$34,072,159 |
| FY 2032 | \$1,300,000 | 45.7      | \$33,955,526 |
| FY 2033 | \$1,300,000 | 45.6      | \$37,575,898 |
| FY 2034 | \$1,300,000 | 45.5      | \$42,358,759 |
| FY 2035 | \$1,300,000 | 45.5      | \$46,935,374 |
| FY 2036 | \$1,300,000 | 45.5      | \$51,216,983 |
| FY 2037 | \$1,300,000 | 45.6      | \$55,674,116 |
| FY 2038 | \$1,300,000 | 45.6      | \$57,200,379 |
| FY 2039 | \$1,300,000 | 45.6      | \$58,241,937 |
| FY 2040 | \$1,300,000 | 45.7      | \$66,807,232 |
| FY 2041 | \$1,300,000 | 45.7      | \$69,146,998 |
| FY 2042 | \$1,300,000 | 45.8      | \$74,665,220 |
| FY 2043 | \$1,300,000 | 45.9      | \$78,958,565 |
| FY 2044 | \$1,300,000 | 46.0      | \$81,596,732 |
| FY 2045 | \$1,300,000 | 46.1      | \$84,128,000 |
| FY 2046 | \$1,300,000 | 46.2      | \$87,218,232 |
| FY 2047 | \$1,300,000 | 46.2      | \$90,341,998 |

The network average PCI slightly drops from a PCI of 47 down to a PCI of 46.2. While this funding level maintains the backlog through FY2029, the backlog

grows significantly to over \$90,000,000 as older water mains reach the end of their service life at the end of the 25-years.

**Figure 19**  
**Summary of Water Main Funding Scenarios**





**11**  
**WATER MAIN  
IMPROVEMENTS  
RECOMMENDATIONS**

# 11. WATER MAIN IMPROVEMENTS RECOMMENDATIONS

## PLAN OF ACTION

The overall water main network in the Town of Holliston is currently in fair condition. However, this study shows that future diligence will be necessary to preserve and improve town-wide water main conditions. The findings in this report illustrate anticipated funding levels are sufficient for the early years of the 25-year planning period but will be insufficient for the increase in water mains that begin coming due for replacement beginning in FY 2029.

The pipe deterioration rates included in this report are theoretical in nature. Actual pipe deterioration rates can be significantly impacted not only by high groundwater levels, which have been theoretically compensated for in this analysis through more aggressive deterioration curves for those pipe segments, but also pressure surges, pipe bedding material, corrosive soils, and electrical currents among other factors. Therefore the Town should supplement this network level tool with actual visual inspection of pipe exteriors. If a pipe segment is due for replacement based on its age, a test pit could be completed to visually inspect the exterior of the pipe to determine if any deterioration is present. Also, when excavation of a pipe segment is required for a service connection or repair, visual pipe observations should be noted since this data can assist with determining if this pipe segment will be due for replacement soon.



# APPENDICES



Appendix A. Backlog of Improvements



| PIPE ID | STREETNAME           | MATERIAL TYPE             | PIPE DIAMETER (INCHES) | LENGTH (FEET) | NPR   | PCI   | REPAIR COST   | REPAIR CATEGORY    |
|---------|----------------------|---------------------------|------------------------|---------------|-------|-------|---------------|--------------------|
| 10      | ALDEN ROAD           | AC - Asbestos Cement      | 6                      | 1140          | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 100     | TRAVIS ROAD          | AC - Asbestos Cement      | 6                      | 863           | 27.87 | 33.22 | \$ -          | Do Nothing         |
| 101     | TURNER ROAD          | AC - Asbestos Cement      | 6                      | 1053          | 30.09 | 5.73  | \$ -          | Do Nothing         |
| 102     | WALNUT ROAD          | AC - Asbestos Cement      | 6                      | 571           | 22.54 | 58.58 | \$ -          | Do Nothing         |
| 103     | WASHINGTON STREET    | AC - Asbestos Cement      | 6                      | 140           | 30.44 | 3.23  | \$ 28,047.60  | Small Pipe (Minor) |
| 104     | WASHINGTON STREET    | AC - Asbestos Cement      | 6                      | 637           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 105     | WEBSTER DRIVE        | AC - Asbestos Cement      | 6                      | 612           | 30.02 | 18.22 | \$ -          | Do Nothing         |
| 106     | WILKINS ROAD         | AC - Asbestos Cement      | 6                      | 1434          | 29.66 | 20.72 | \$ -          | Do Nothing         |
| 107     | WINTER STREET        | AC - Asbestos Cement      | 6                      | 2293          | 26.43 | 96.65 | \$ -          | Do Nothing         |
| 108     | AVON STREET          | AC - Asbestos Cement      | 6                      | 80            | 30.44 | 3.23  | \$ 16,027.20  | Small Pipe (Minor) |
| 109     | CENTRAL STREET       | AC - Asbestos Cement      | 6                      | 1024          | 32.62 | 0     | \$ 205,148.16 | Small Pipe (Minor) |
| 11      | APPLEYARD LANE       | AC - Asbestos Cement      | 6                      | 1137          | 18.81 | 96.65 | \$ -          | Do Nothing         |
| 110     | WASHINGTON STREET    | DI - Ductile Iron         | 12                     | 191           | 19.6  | 79.15 | \$ -          | Do Nothing         |
| 111     | FRANCINE DRIVE       | AC - Asbestos Cement      | 6                      | 1046          | 25.44 | 38.22 | \$ -          | Do Nothing         |
| 112     | HIGHLAND STREET      | PVC - Poly Vinyl Chloride | 12                     | 346           | 19.38 | 80.65 | \$ -          | Do Nothing         |
| 113     | LOWLAND STREET       | AC - Asbestos Cement      | 12                     | 251           | 24.37 | 45.72 | \$ -          | Do Nothing         |
| 114     | MAPLE STREET         | DI - Ductile Iron         | 6                      | 675           | 24.25 | 46.58 | \$ -          | Do Nothing         |
| 115     | MAPLE STREET         | DI - Ductile Iron         | 6                      | 63            | 29.01 | 46.58 | \$ -          | Do Nothing         |
| 116     | MAPLE STREET         | DI - Ductile Iron         | 6                      | 1330          | 25.96 | 46.58 | \$ -          | Do Nothing         |
| 117     | NORTH MILL STREET    | DI - Ductile Iron         | 6                      | 595           | 24.93 | 75.15 | \$ -          | Do Nothing         |
| 118     | OAK STREET           | AC - Asbestos Cement      | 6                      | 60            | 29.37 | 10.73 | \$ -          | Do Nothing         |
| 119     | PLEASANT STREET      | AC - Asbestos Cement      | 6                      | 692           | 26.52 | 30.72 | \$ -          | Do Nothing         |
| 12      | ASHLAND STREET       | AC - Asbestos Cement      | 6                      | 2428          | 35.48 | 0     | \$ 486,425.52 | Small Pipe (Minor) |
| 120     | POND VIEW            | DI - Ductile Iron         | 6                      | 3111          | 18.53 | 86.65 | \$ -          | Do Nothing         |
| 121     | SCHOOL STREET        | AC - Asbestos Cement      | 6                      | 505           | 17.1  | 96.65 | \$ -          | Do Nothing         |
| 122     | TRACY LYN ROAD       | AC - Asbestos Cement      | 6                      | 1116          | 26.52 | 30.72 | \$ -          | Do Nothing         |
| 123     | TRAVIS ROAD          | DI - Ductile Iron         | 6                      | 983           | 20.67 | 71.65 | \$ -          | Do Nothing         |
| 124     | WASHINGTON STREET    | AC - Asbestos Cement      | 8                      | 76            | 30.44 | 3.23  | \$ 15,225.84  | Small Pipe (Minor) |
| 125     | WASHINGTON STREET    | DI - Ductile Iron         | 12                     | 98            | 19.6  | 79.15 | \$ -          | Do Nothing         |
| 126     | WENDY LANE           | DI - Ductile Iron         | 6                      | 473           | 42.22 | 79.15 | \$ -          | Do Nothing         |
| 127     | GOULDING PLACE       | PVC - Poly Vinyl Chloride | 6                      | 590           | 17.81 | 91.65 | \$ -          | Do Nothing         |
| 128     | BOGASTOW BOOK ROAD   | AC - Asbestos Cement      | 6                      | 469           | 22.82 | 56.58 | \$ -          | Do Nothing         |
| 129     | ROBIN HILL DRIVE     | AC - Asbestos Cement      | 6                      | 487           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 13      | AVON STREET          | AC - Asbestos Cement      | 6                      | 787           | 26.16 | 33.22 | \$ -          | Do Nothing         |
| 130     | ROLLING MEADOW DRIVE | PVC - Poly Vinyl Chloride | 6                      | 3458          | 19.38 | 80.65 | \$ -          | Do Nothing         |
| 131     | ROBIN HILL DRIVE     | PVC - Poly Vinyl Chloride | 6                      | 1624          | 19.24 | 81.65 | \$ -          | Do Nothing         |
| 132     | EVERETT STREET       | PVC - Poly Vinyl Chloride | 6                      | 663           | 19.31 | 81.15 | \$ -          | Do Nothing         |
| 133     | WHITNEY STREET       | PVC - Poly Vinyl Chloride | 6                      | 397           | 24.15 | 80.65 | \$ -          | Do Nothing         |
| 134     | RALEIGH ROAD         | PVC - Poly Vinyl Chloride | 8                      | 567           | 18.38 | 87.65 | \$ -          | Do Nothing         |
| 135     | PARTRIDGE WAY        | PVC - Poly Vinyl Chloride | 8                      | 1105          | 18.38 | 87.65 | \$ -          | Do Nothing         |
| 136     | MANCHESTER           | PVC - Poly Vinyl Chloride | 8                      | 308           | 18.38 | 87.65 | \$ -          | Do Nothing         |
| 137     | PARTRIDGE WAY        | PVC - Poly Vinyl Chloride | 8                      | 600           | 18.38 | 87.65 | \$ -          | Do Nothing         |
| 138     | RALEIGH ROAD         | PVC - Poly Vinyl Chloride | 8                      | 377           | 18.38 | 87.65 | \$ -          | Do Nothing         |
| 139     | ADAMS STREET         | AC - Asbestos Cement      | 8                      | 1873          | 27.59 | 23.22 | \$ -          | Do Nothing         |
| 14      | BAYBERRY LANE        | AC - Asbestos Cement      | 6                      | 982           | 25.8  | 35.72 | \$ -          | Do Nothing         |
| 140     | ANDREW LANE          | AC - Asbestos Cement      | 8                      | 1362          | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 141     | ANNE MARIE DRIVE     | AC - Asbestos Cement      | 8                      | 1246          | 25.44 | 38.22 | \$ -          | Do Nothing         |
| 142     | ASHLAND STREET       | AC - Asbestos Cement      | 8                      | 278           | 30.9  | 0     | \$ 55,694.52  | Small Pipe (Minor) |
| 143     | BAKER STREET         | AC - Asbestos Cement      | 8                      | 1111          | 26.52 | 30.72 | \$ -          | Do Nothing         |
| 144     | BOGASTOW BOOK ROAD   | AC - Asbestos Cement      | 8                      | 1147          | 24.82 | 54.58 | \$ -          | Do Nothing         |
| 145     | BONNEY DRIVE         | AC - Asbestos Cement      | 8                      | 2083          | 24.37 | 45.72 | \$ -          | Do Nothing         |
| 146     | BRIARCLIFF LANE      | AC - Asbestos Cement      | 8                      | 1844          | 21.96 | 62.58 | \$ -          | Do Nothing         |
| 147     | BROOK STREET         | AC - Asbestos Cement      | 8                      | 1095          | 29.14 | 45.72 | \$ -          | Do Nothing         |
| 148     | BULLARD STREET       | AC - Asbestos Cement      | 8                      | 1274          | 27.87 | 54.58 | \$ -          | Do Nothing         |

| PIPE ID | STREETNAME         | MATERIAL TYPE             | PIPE DIAMETER (INCHES) | LENGTH (FEET) | NPR   | PCI   | REPAIR COST   | REPAIR CATEGORY    |
|---------|--------------------|---------------------------|------------------------|---------------|-------|-------|---------------|--------------------|
| 149     | BURNAP ROAD        | AC - Asbestos Cement      | 8                      | 1091          | 25.8  | 35.72 | \$ -          | Do Nothing         |
| 15      | BEVERLY CIRCLE     | PVC - Poly Vinyl Chloride | 8                      | 417           | 19.1  | 82.65 | \$ -          | Do Nothing         |
| 150     | CARL ROAD          | AC - Asbestos Cement      | 8                      | 570           | 25.8  | 35.72 | \$ -          | Do Nothing         |
| 151     | CEDAR ROAD         | AC - Asbestos Cement      | 8                      | 462           | 30.44 | 3.23  | \$ 92,557.08  | Small Pipe (Minor) |
| 152     | CEDAR STREET       | AC - Asbestos Cement      | 8                      | 2837          | 26.43 | 96.65 | \$ -          | Do Nothing         |
| 153     | CENTRAL STREET     | AC - Asbestos Cement      | 8                      | 3818          | 23.68 | 50.58 | \$ -          | Do Nothing         |
| 154     | CENTRAL STREET     | AC - Asbestos Cement      | 8                      | 1268          | 23.68 | 50.58 | \$ -          | Do Nothing         |
| 155     | CENTRAL STREET     | AC - Asbestos Cement      | 8                      | 2570          | 24.37 | 45.72 | \$ -          | Do Nothing         |
| 156     | CENTRAL STREET     | AC - Asbestos Cement      | 8                      | 641           | 18.86 | 84.29 | \$ -          | Do Nothing         |
| 157     | CHAMBERLAIN STREET | AC - Asbestos Cement      | 8                      | 523           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 158     | CHARLES STREET     | AC - Asbestos Cement      | 6                      | 987           | 28.3  | 18.22 | \$ -          | Do Nothing         |
| 159     | CHURCH PLACE       | AC - Asbestos Cement      | 8                      | 285           | 30.44 | 3.23  | \$ 57,096.90  | Small Pipe (Minor) |
| 16      | BIRCH ROAD         | AC - Asbestos Cement      | 6                      | 934           | 24.02 | 48.22 | \$ -          | Do Nothing         |
| 160     | CHURCH STREET      | AC - Asbestos Cement      | 8                      | 2431          | 23.68 | 62.58 | \$ -          | Do Nothing         |
| 161     | CONCORD STREET     | AC - Asbestos Cement      | 8                      | 1702          | 45    | 0     | \$ 426,214.84 | Small Pipe (Major) |
| 162     | CURVE STREET       | AC - Asbestos Cement      | 8                      | 434           | 25.09 | 40.72 | \$ -          | Do Nothing         |
| 163     | DALTON ROAD        | AC - Asbestos Cement      | 8                      | 3507          | 23.39 | 64.58 | \$ -          | Do Nothing         |
| 164     | DAY ROAD           | AC - Asbestos Cement      | 8                      | 514           | 26.52 | 30.72 | \$ -          | Do Nothing         |
| 165     | DUNSTER ROAD       | AC - Asbestos Cement      | 8                      | 1257          | 25.8  | 35.72 | \$ -          | Do Nothing         |
| 166     | DODD DRIVE         | AC - Asbestos Cement      | 8                      | 1538          | 24.37 | 45.72 | \$ -          | Do Nothing         |
| 167     | ELM STREET         | AC - Asbestos Cement      | 8                      | 528           | 34.78 | 18.22 | \$ -          | Do Nothing         |
| 168     | EXCHANGE STREET    | AC - Asbestos Cement      | 8                      | 1453          | 21.86 | 96.65 | \$ -          | Do Nothing         |
| 169     | FISKE STREET       | AC - Asbestos Cement      | 8                      | 1158          | 53.52 | 0     | \$ 231,993.72 | Small Pipe (Minor) |
| 17      | BIRCHWOOD DRIVE    | AC - Asbestos Cement      | 6                      | 1446          | 17.1  | 96.65 | \$ -          | Do Nothing         |
| 170     | FRANCINE DRIVE     | AC - Asbestos Cement      | 8                      | 531           | 25.44 | 38.22 | \$ -          | Do Nothing         |
| 171     | FRUIT STREET       | AC - Asbestos Cement      | 8                      | 449           | 24.73 | 43.22 | \$ -          | Do Nothing         |
| 172     | GORWIN DRIVE       | AC - Asbestos Cement      | 8                      | 1524          | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 173     | GOULDING STREET    | AC - Asbestos Cement      | 8                      | 2299          | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 174     | GRANITE STREET     | AC - Asbestos Cement      | 8                      | 1153          | 26.52 | 30.72 | \$ -          | Do Nothing         |
| 175     | GRETCHEN LANE      | AC - Asbestos Cement      | 8                      | 1045          | 24.02 | 48.22 | \$ -          | Do Nothing         |
| 176     | GROVE STREET       | AC - Asbestos Cement      | 8                      | 297           | 30.02 | 18.22 | \$ -          | Do Nothing         |
| 177     | GORWIN DRIVE       | AC - Asbestos Cement      | 8                      | 1188          | 26.16 | 33.22 | \$ -          | Do Nothing         |
| 178     | HANLON ROAD        | AC - Asbestos Cement      | 8                      | 1107          | 30.92 | 33.22 | \$ -          | Do Nothing         |
| 179     | HARGRAVE AVENUE    | AC - Asbestos Cement      | 8                      | 302           | 25.09 | 40.72 | \$ -          | Do Nothing         |
| 18      | BRADFORD JAY ROAD  | AC - Asbestos Cement      | 6                      | 1002          | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 180     | HIGH STREET        | AC - Asbestos Cement      | 8                      | 2030          | 30.9  | 0     | \$ 508,352.60 | Small Pipe (Major) |
| 181     | HIGHLAND STREET    | AC - Asbestos Cement      | 12                     | 1027          | 26.87 | 28.22 | \$ -          | Do Nothing         |
| 182     | IRVING PLACE       | AC - Asbestos Cement      | 8                      | 467           | 22.25 | 60.58 | \$ -          | Do Nothing         |
| 183     | JEFFREY AVENUE     | PVC - Poly Vinyl Chloride | 8                      | 1677          | 19.38 | 80.65 | \$ -          | Do Nothing         |
| 184     | JENNINGS ROAD      | AC - Asbestos Cement      | 8                      | 1402          | 24.37 | 45.72 | \$ -          | Do Nothing         |
| 185     | KAREN CIRCLE       | AC - Asbestos Cement      | 8                      | 2251          | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 186     | KATHERYN AVENUE    | AC - Asbestos Cement      | 8                      | 412           | 24.37 | 45.72 | \$ -          | Do Nothing         |
| 187     | LITTLE ROAD        | AC - Asbestos Cement      | 8                      | 357           | 26.16 | 33.22 | \$ -          | Do Nothing         |
| 188     | MARSHALL STREET    | AC - Asbestos Cement      | 8                      | 1894          | 26.16 | 33.22 | \$ -          | Do Nothing         |
| 189     | MARY CHRIS ROAD    | AC - Asbestos Cement      | 8                      | 389           | 25.44 | 38.22 | \$ -          | Do Nothing         |
| 19      | BROOK STREET       | AC - Asbestos Cement      | 6                      | 395           | 29.14 | 45.72 | \$ -          | Do Nothing         |
| 190     | MEADERS ROW        | AC - Asbestos Cement      | 8                      | 247           | 29.14 | 45.72 | \$ -          | Do Nothing         |
| 191     | MECHANIC STREET    | AC - Asbestos Cement      | 8                      | 1600          | 17.1  | 96.65 | \$ -          | Do Nothing         |
| 192     | MILL STREET        | AC - Asbestos Cement      | 8                      | 900           | 24.37 | 45.72 | \$ -          | Do Nothing         |
| 193     | NORFOLK STREET     | AC - Asbestos Cement      | 8                      | 1445          | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 194     | NORFOLK STREET     | AC - Asbestos Cement      | 8                      | 325           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 195     | NORTH MILL STREET  | AC - Asbestos Cement      | 8                      | 496           | 29.85 | 40.72 | \$ -          | Do Nothing         |
| 196     | NORTH MILL STREET  | AC - Asbestos Cement      | 8                      | 372           | 23.68 | 50.58 | \$ -          | Do Nothing         |
| 197     | OAK STREET         | AC - Asbestos Cement      | 8                      | 1490          | 28.3  | 18.22 | \$ -          | Do Nothing         |

| PIPE ID | STREETNAME        | MATERIAL TYPE             | PIPE DIAMETER (INCHES) | LENGTH (FEET) | NPR   | PCI   | REPAIR COST   | REPAIR CATEGORY    |
|---------|-------------------|---------------------------|------------------------|---------------|-------|-------|---------------|--------------------|
| 198     | PILGRIM DRIVE     | AC - Asbestos Cement      | 8                      | 1146          | 22.54 | 58.58 | \$ -          | Do Nothing         |
| 199     | PINE OAK STREET   | AC - Asbestos Cement      | 8                      | 339           | 26.87 | 28.22 | \$ -          | Do Nothing         |
| 20      | BYRON ROAD        | PVC - Poly Vinyl Chloride | 6                      | 422           | 19.17 | 82.15 | \$ -          | Do Nothing         |
| 200     | PINECREST ROAD    | AC - Asbestos Cement      | 8                      | 2244          | 17.1  | 96.65 | \$ -          | Do Nothing         |
| 201     | PRENTICE STREET   | AC - Asbestos Cement      | 8                      | 2042          | 29.37 | 10.73 | \$ -          | Do Nothing         |
| 202     | QUEENS TERRACE    | AC - Asbestos Cement      | 8                      | 1097          | 23.68 | 50.58 | \$ -          | Do Nothing         |
| 203     | RICHARD ROAD      | AC - Asbestos Cement      | 8                      | 1881          | 25.44 | 38.22 | \$ -          | Do Nothing         |
| 204     | ROY AVENUE        | AC - Asbestos Cement      | 8                      | 357           | 26.52 | 30.72 | \$ -          | Do Nothing         |
| 205     | RUTHELLEN STREET  | AC - Asbestos Cement      | 8                      | 1771          | 25.44 | 38.22 | \$ -          | Do Nothing         |
| 206     | SCOTT DRIVE       | AC - Asbestos Cement      | 8                      | 405           | 26.52 | 30.72 | \$ -          | Do Nothing         |
| 207     | SHORT ROAD        | AC - Asbestos Cement      | 8                      | 322           | 25.8  | 35.72 | \$ -          | Do Nothing         |
| 208     | SMITHS ROW        | AC - Asbestos Cement      | 8                      | 219           | 30.44 | 3.23  | \$ 43,874.46  | Small Pipe (Minor) |
| 209     | SOUTH STREET      | AC - Asbestos Cement      | 8                      | 3644          | 23.39 | 52.58 | \$ -          | Do Nothing         |
| 21      | CABOT ROAD        | AC - Asbestos Cement      | 6                      | 934           | 22.82 | 56.58 | \$ -          | Do Nothing         |
| 210     | SPRING STREET     | AC - Asbestos Cement      | 8                      | 592           | 17.1  | 96.65 | \$ -          | Do Nothing         |
| 211     | STONEBROOK DRIVE  | AC - Asbestos Cement      | 8                      | 3125          | 25.39 | 50.58 | \$ -          | Do Nothing         |
| 212     | SUMMER STREET     | AC - Asbestos Cement      | 8                      | 1859          | 32.62 | 0     | \$ 465,530.78 | Small Pipe (Major) |
| 213     | TEMI ROAD         | AC - Asbestos Cement      | 8                      | 702           | 25.8  | 35.72 | \$ -          | Do Nothing         |
| 214     | TURNER ROAD       | AC - Asbestos Cement      | 8                      | 1580          | 30.37 | 35.72 | \$ -          | Do Nothing         |
| 215     | UNDERWOOD STREET  | AC - Asbestos Cement      | 8                      | 1490          | 29.37 | 10.73 | \$ -          | Do Nothing         |
| 216     | UNION STREET      | AC - Asbestos Cement      | 8                      | 1500          | 18.81 | 96.65 | \$ -          | Do Nothing         |
| 217     | VINE STREET       | AC - Asbestos Cement      | 8                      | 468           | 22.54 | 58.58 | \$ -          | Do Nothing         |
| 218     | WASHINGTON STREET | AC - Asbestos Cement      | 8                      | 3183          | 30.44 | 3.23  | \$ 797,086.86 | Small Pipe (Major) |
| 219     | WASHINGTON STREET | AC - Asbestos Cement      | 8                      | 841           | 60    | 0     | \$ 210,603.22 | Small Pipe (Major) |
| 22      | CARLTON DRIVE     | AC - Asbestos Cement      | 6                      | 616           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 220     | WASHINGTON STREET | AC - Asbestos Cement      | 8                      | 613           | 30.44 | 3.23  | \$ 153,507.46 | Small Pipe (Major) |
| 221     | WASHINGTON STREET | AC - Asbestos Cement      | 8                      | 282           | 30.44 | 3.23  | \$ 56,495.88  | Small Pipe (Minor) |
| 222     | WATER STREET      | AC - Asbestos Cement      | 8                      | 1796          | 31.64 | 28.22 | \$ -          | Do Nothing         |
| 223     | WINCHESTER DRIVE  | AC - Asbestos Cement      | 8                      | 1151          | 25.11 | 52.58 | \$ -          | Do Nothing         |
| 224     | WINDGATE ROAD     | AC - Asbestos Cement      | 8                      | 2468          | 25.44 | 38.22 | \$ -          | Do Nothing         |
| 225     | WINDSOR DRIVE     | AC - Asbestos Cement      | 8                      | 685           | 21.68 | 64.58 | \$ -          | Do Nothing         |
| 226     | WINSTON ROAD      | PVC - Poly Vinyl Chloride | 8                      | 506           | 20.88 | 82.15 | \$ -          | Do Nothing         |
| 227     | WINTER STREET     | AC - Asbestos Cement      | 8                      | 2155          | 17.1  | 96.65 | \$ -          | Do Nothing         |
| 228     | WINTHROP STREET   | AC - Asbestos Cement      | 8                      | 2306          | 26.09 | 45.72 | \$ -          | Do Nothing         |
| 229     | ELM STREET        | CI - Cast Iron            | 8                      | 467           | 32.88 | 24.87 | \$ 41,301.48  | Cement Line        |
| 23      | CHERYL LANE       | AC - Asbestos Cement      | 6                      | 1707          | 21.67 | 96.65 | \$ -          | Do Nothing         |
| 230     | BOYTON ROAD       | DI - Ductile Iron         | 8                      | 665           | 19.17 | 82.15 | \$ -          | Do Nothing         |
| 231     | DEER RUN ROAD     | DI - Ductile Iron         | 8                      | 748           | 18.45 | 87.15 | \$ -          | Do Nothing         |
| 232     | MAYFLOWER LANDING | DI - Ductile Iron         | 8                      | 915           | 23    | 88.65 | \$ -          | Do Nothing         |
| 236     | ALPINE DRIVE      | DI - Ductile Iron         | 8                      | 953           | 19.17 | 82.15 | \$ -          | Do Nothing         |
| 237     | BALD HILL ROAD    | DI - Ductile Iron         | 8                      | 1502          | 19.14 | 82.32 | \$ -          | Do Nothing         |
| 238     | BOULDER ROAD      | DI - Ductile Iron         | 8                      | 678           | 18.31 | 88.15 | \$ -          | Do Nothing         |
| 239     | CASSANDRA LANE    | DI - Ductile Iron         | 8                      | 1611          | 18.6  | 86.15 | \$ -          | Do Nothing         |
| 24      | CHRISTOPHER ROAD  | AC - Asbestos Cement      | 6                      | 1116          | 26.52 | 30.72 | \$ -          | Do Nothing         |
| 240     | COUNTRY ROAD      | DI - Ductile Iron         | 8                      | 1026          | 19.88 | 77.15 | \$ -          | Do Nothing         |
| 241     | ERIN WAY          | DI - Ductile Iron         | 8                      | 640           | 19.1  | 82.65 | \$ -          | Do Nothing         |
| 242     | FOREST PARK DRIVE | DI - Ductile Iron         | 8                      | 1324          | 22.79 | 90.15 | \$ -          | Do Nothing         |
| 243     | GREAT MEADOW ROAD | DI - Ductile Iron         | 8                      | 1000          | 18.88 | 84.15 | \$ -          | Do Nothing         |
| 244     | HARNESS LANE      | DI - Ductile Iron         | 8                      | 371           | 18.6  | 86.15 | \$ -          | Do Nothing         |
| 245     | JOHNSON DRIVE     | DI - Ductile Iron         | 8                      | 421           | 18.53 | 86.65 | \$ -          | Do Nothing         |
| 246     | LONE OAK CIRCLE   | DI - Ductile Iron         | 8                      | 581           | 19.6  | 79.15 | \$ -          | Do Nothing         |
| 247     | MORGANS WAY       | DI - Ductile Iron         | 8                      | 3180          | 19.03 | 83.15 | \$ -          | Do Nothing         |
| 248     | NOEL DRIVE        | DI - Ductile Iron         | 8                      | 1472          | 18.31 | 88.15 | \$ -          | Do Nothing         |
| 249     | NORLAND STREET    | AC - Asbestos Cement      | 8                      | 2769          | 29.37 | 10.73 | \$ -          | Do Nothing         |

Appendix A. Backlog of Improvements



| PIPE ID | STREETNAME         | MATERIAL TYPE             | PIPE DIAMETER (INCHES) | LENGTH (FEET) | NPR   | PCI   | REPAIR COST     | REPAIR CATEGORY     |
|---------|--------------------|---------------------------|------------------------|---------------|-------|-------|-----------------|---------------------|
| 25      | COLD SPRINGS ROAD  | AC - Asbestos Cement      | 6                      | 1048          | 18.81 | 96.65 | \$ -            | Do Nothing          |
| 250     | PAUL ROAD          | AC - Asbestos Cement      | 8                      | 1099          | 27.87 | 33.22 | \$ -            | Do Nothing          |
| 251     | PRENTICE STREET    | DI - Ductile Iron         | 8                      | 869           | 23.72 | 83.65 | \$ -            | Do Nothing          |
| 252     | SABINA DRIVE       | DI - Ductile Iron         | 8                      | 725           | 18.53 | 86.65 | \$ -            | Do Nothing          |
| 253     | SHAW FARM ROAD     | DI - Ductile Iron         | 8                      | 1387          | 17.95 | 90.65 | \$ -            | Do Nothing          |
| 254     | SOUTH STREET       | DI - Ductile Iron         | 8                      | 808           | 20.1  | 75.65 | \$ -            | Do Nothing          |
| 255     | TEMI ROAD          | AC - Asbestos Cement      | 8                      | 906           | 26.16 | 33.22 | \$ -            | Do Nothing          |
| 256     | TIMBER LEDGE DRIVE | DI - Ductile Iron         | 8                      | 770           | 18.53 | 86.65 | \$ -            | Do Nothing          |
| 257     | UNDERWOOD STREET   | AC - Asbestos Cement      | 8                      | 433           | 33.94 | 10.73 | \$ -            | Do Nothing          |
| 258     | WASHINGTON STREET  | AC - Asbestos Cement      | 8                      | 2873          | 58.1  | 0     | \$ 719,456.66   | Small Pipe (Major)  |
| 259     | WEDGEWOOD DRIVE    | AC - Asbestos Cement      | 8                      | 1633          | 28.66 | 15.72 | \$ -            | Do Nothing          |
| 26      | COLONIAL WAY       | AC - Asbestos Cement      | 6                      | 306           | 27.82 | 21.58 | \$ -            | Do Nothing          |
| 260     | WHISPERING LANE    | DI - Ductile Iron         | 8                      | 266           | 18.31 | 88.15 | \$ -            | Do Nothing          |
| 261     | WHISPERING LANE    | DI - Ductile Iron         | 8                      | 1926          | 18.53 | 86.65 | \$ -            | Do Nothing          |
| 262     | WHITE PINE DRIVE   | DI - Ductile Iron         | 8                      | 1711          | 19.03 | 83.15 | \$ -            | Do Nothing          |
| 263     | WOODS CROSSING     | DI - Ductile Iron         | 8                      | 1800          | 18.38 | 87.65 | \$ -            | Do Nothing          |
| 264     | OVERLOOK DRIVE     | PVC - Poly Vinyl Chloride | 8                      | 2587          | 19.53 | 79.65 | \$ -            | Do Nothing          |
| 265     | ALBERTA LANE       | PVC - Poly Vinyl Chloride | 8                      | 1133          | 18.67 | 85.65 | \$ -            | Do Nothing          |
| 266     | AMY LANE           | PVC - Poly Vinyl Chloride | 8                      | 1195          | 19.03 | 83.15 | \$ -            | Do Nothing          |
| 267     | BEAVER BROOK DRIVE | PVC - Poly Vinyl Chloride | 8                      | 561           | 18.67 | 85.65 | \$ -            | Do Nothing          |
| 268     | FAIRVIEW STREET    | PVC - Poly Vinyl Chloride | 8                      | 3331          | 23.15 | 87.65 | \$ -            | Do Nothing          |
| 269     | FISKE POND ROAD    | PVC - Poly Vinyl Chloride | 8                      | 1344          | 24.22 | 80.15 | \$ -            | Do Nothing          |
| 27      | COPPER LANE        | AC - Asbestos Cement      | 6                      | 614           | 27.94 | 20.72 | \$ -            | Do Nothing          |
| 270     | GORWIN DRIVE       | PVC - Poly Vinyl Chloride | 8                      | 565           | 18.38 | 87.65 | \$ -            | Do Nothing          |
| 271     | HILLSIDE DRIVE     | PVC - Poly Vinyl Chloride | 8                      | 1880          | 23.43 | 85.65 | \$ -            | Do Nothing          |
| 272     | HOLLIS STREET      | AC - Asbestos Cement      | 8                      | 2812          | 30.9  | 0     | \$ 563,356.08   | Small Pipe (Minor)  |
| 273     | JOHNSON DRIVE      | PVC - Poly Vinyl Chloride | 8                      | 2908          | 23.36 | 86.15 | \$ -            | Do Nothing          |
| 274     | OLD SAWMILL ROAD   | PVC - Poly Vinyl Chloride | 8                      | 1918          | 18.67 | 85.65 | \$ -            | Do Nothing          |
| 275     | PAMALA DRIVE       | PVC - Poly Vinyl Chloride | 8                      | 1717          | 21.17 | 80.15 | \$ -            | Do Nothing          |
| 276     | ROGERS STREET      | PVC - Poly Vinyl Chloride | 8                      | 1000          | 24.07 | 81.15 | \$ -            | Do Nothing          |
| 277     | SADDLE RIDGE ROAD  | PVC - Poly Vinyl Chloride | 8                      | 416           | 18.6  | 86.15 | \$ -            | Do Nothing          |
| 278     | WHITNEY STREET     | PVC - Poly Vinyl Chloride | 8                      | 1535          | 24.15 | 80.65 | \$ -            | Do Nothing          |
| 279     | WILSON STREET      | PVC - Poly Vinyl Chloride | 8                      | 278           | 22.43 | 92.65 | \$ -            | Do Nothing          |
| 28      | COTTAGE DRIVE      | AC - Asbestos Cement      | 6                      | 916           | 22.82 | 56.58 | \$ -            | Do Nothing          |
| 280     | NORFOLK STREET     | ST - Steel                | 8                      | 2384          | 22.15 | 73.29 | \$ -            | Do Nothing          |
| 281     | STODDARD PARK ROAD | ST - Steel                | 8                      | 1043          | 21.15 | 68.29 | \$ -            | Do Nothing          |
| 282     | CHAMBERLAIN STREET | AC - Asbestos Cement      | 10                     | 2150          | 27.94 | 20.72 | \$ -            | Do Nothing          |
| 283     | CHAMBERLAIN STREET | AC - Asbestos Cement      | 10                     | 1561          | 27.94 | 20.72 | \$ -            | Do Nothing          |
| 284     | DODD DRIVE         | AC - Asbestos Cement      | 10                     | 415           | 26.16 | 33.22 | \$ -            | Do Nothing          |
| 285     | FRANKLIN STREET    | AC - Asbestos Cement      | 10                     | 927           | 23.39 | 52.58 | \$ -            | Do Nothing          |
| 286     | NORFOLK STREET     | AC - Asbestos Cement      | 10                     | 1377          | 25.8  | 35.72 | \$ -            | Do Nothing          |
| 287     | WASHINGTON STREET  | AC - Asbestos Cement      | 10                     | 1771          | 40.24 | 0     | \$ 532,203.21   | Medium Pipe (Major) |
| 288     | WASHINGTON STREET  | AC - Asbestos Cement      | 10                     | 2304          | 39.78 | 3.23  | \$ 692,375.04   | Medium Pipe (Major) |
| 289     | WESTFIELD DRIVE    | AC - Asbestos Cement      | 10                     | 1513          | 45.37 | 30.72 | \$ -            | Do Nothing          |
| 29      | CRANBERRY LANE     | AC - Asbestos Cement      | 6                      | 1440          | 26.16 | 33.22 | \$ -            | Do Nothing          |
| 291     | HOPPING BROOK ROAD | DI - Ductile Iron         | 10                     | 3087          | 19.17 | 82.15 | \$ -            | Do Nothing          |
| 293     | CENTRAL STREET     | AC - Asbestos Cement      | 12                     | 1491          | 23.68 | 50.58 | \$ -            | Do Nothing          |
| 294     | CONCORD STREET     | AC - Asbestos Cement      | 12                     | 3761          | 44.54 | 3.23  | \$ 1,130,218.11 | Medium Pipe (Major) |
| 295     | HIGHLAND STREET    | AC - Asbestos Cement      | 12                     | 1799          | 28.59 | 28.22 | \$ -            | Do Nothing          |
| 296     | LOWLAND STREET     | AC - Asbestos Cement      | 12                     | 2344          | 24.37 | 45.72 | \$ -            | Do Nothing          |
| 297     | WASHINGTON STREET  | AC - Asbestos Cement      | 12                     | 2310          | 32.16 | 3.23  | \$ 694,178.10   | Medium Pipe (Major) |
| 298     | UNDERWOOD STREET   | AC - Asbestos Cement      | 12                     | 1652          | 29.37 | 10.73 | \$ -            | Do Nothing          |
| 299     | OLD LOCUST ST      | DI - Ductile Iron         | 12                     | 1900          | 23    | 88.65 | \$ -            | Do Nothing          |
| 30      | CYNTHIA CIRCLE     | DI - Ductile Iron         | 6                      | 105           | 19.67 | 90.65 | \$ -            | Do Nothing          |

Appendix A. Backlog of Improvements



| PIPE ID | STREETNAME         | MATERIAL TYPE             | PIPE DIAMETER (INCHES) | LENGTH (FEET) | NPR   | PCI   | REPAIR COST   | REPAIR CATEGORY     |
|---------|--------------------|---------------------------|------------------------|---------------|-------|-------|---------------|---------------------|
| 301     | OLD CART PATH      | DI - Ductile Iron         | 12                     | 3750          | 18.45 | 87.15 | \$ -          | Do Nothing          |
| 302     | ASHLAND STREET     | AC - Asbestos Cement      | 12                     | 696           | 35.67 | 0     | \$ 174,292.32 | Medium Pipe (Minor) |
| 303     | CONCORD STREET     | DI - Ductile Iron         | 12                     | 1921          | 24.07 | 81.15 | \$ -          | Do Nothing          |
| 304     | COURTLAND STREET   | DI - Ductile Iron         | 12                     | 879           | 23.22 | 87.15 | \$ -          | Do Nothing          |
| 305     | FISKE STREET       | DI - Ductile Iron         | 12                     | 920           | 18.17 | 89.15 | \$ -          | Do Nothing          |
| 306     | HANLON ROAD        | DI - Ductile Iron         | 12                     | 1178          | 19.17 | 82.15 | \$ -          | Do Nothing          |
| 307     | HIGHLAND STREET    | DI - Ductile Iron         | 12                     | 2863          | 17.95 | 90.65 | \$ -          | Do Nothing          |
| 308     | LINDEN STREET      | DI - Ductile Iron         | 12                     | 1592          | 22.74 | 89.15 | \$ -          | Do Nothing          |
| 309     | MARSHALL STREET    | DI - Ductile Iron         | 12                     | 2753          | 23.65 | 84.15 | \$ -          | Do Nothing          |
| 31      | DAVID STREET       | AC - Asbestos Cement      | 6                      | 682           | 26.52 | 30.72 | \$ -          | Do Nothing          |
| 310     | PRENTICE STREET    | DI - Ductile Iron         | 12                     | 2556          | 25    | 74.65 | \$ -          | Do Nothing          |
| 311     | WASHINGTON STREET  | DI - Ductile Iron         | 12                     | 1205          | 19.53 | 79.65 | \$ -          | Do Nothing          |
| 312     | WASHINGTON STREET  | AC - Asbestos Cement      | 12                     | 603           | 32.16 | 3.23  | \$ 181,207.53 | Medium Pipe (Major) |
| 313     | WASHINGTON STREET  | DI - Ductile Iron         | 12                     | 3613          | 24.17 | 79.15 | \$ -          | Do Nothing          |
| 314     | WOODLAND STREET    | DI - Ductile Iron         | 12                     | 4400          | 20.95 | 81.65 | \$ -          | Do Nothing          |
| 315     | HIGHLAND STREET    | PVC - Poly Vinyl Chloride | 12                     | 3080          | 19.45 | 80.15 | \$ -          | Do Nothing          |
| 316     | HIGHLAND STREET    | PVC - Poly Vinyl Chloride | 12                     | 1274          | 22.72 | 57.29 | \$ -          | Do Nothing          |
| 317     | MARSHALL STREET    | PVC - Poly Vinyl Chloride | 12                     | 2064          | 19.31 | 81.15 | \$ -          | Do Nothing          |
| 318     | WILLOWGATE RISE    | PVC - Poly Vinyl Chloride | 12                     | 2700          | 24.1  | 79.65 | \$ -          | Do Nothing          |
| 319     | BEATRICE STREET    | DI - Ductile Iron         | 16                     | 1689          | 18.45 | 87.15 | \$ -          | Do Nothing          |
| 32      | DEAN ROAD          | AC - Asbestos Cement      | 6                      | 438           | 30.44 | 3.23  | \$ 87,748.92  | Small Pipe (Minor)  |
| 320     | CHURCH PLACE       | DI - Ductile Iron         | 16                     | 655           | 20.45 | 73.15 | \$ -          | Do Nothing          |
| 321     | ADAMS STREET       | AC - Asbestos Cement      | 8                      | 1389          | 27.59 | 23.22 | \$ -          | Do Nothing          |
| 322     | ADAMS STREET       | AC - Asbestos Cement      | 8                      | 1395          | 32.35 | 23.22 | \$ -          | Do Nothing          |
| 323     | ADAMS STREET       | AC - Asbestos Cement      | 8                      | 1836          | 27.59 | 23.22 | \$ -          | Do Nothing          |
| 324     | WASHINGTON STREET  | AC - Asbestos Cement      | 8                      | 807           | 55.24 | 0     | \$ 202,088.94 | Small Pipe (Major)  |
| 325     | WASHINGTON STREET  | AC - Asbestos Cement      | 8                      | 598           | 58.29 | 0     | \$ 149,751.16 | Small Pipe (Major)  |
| 326     | CONCORD STREET     | DI - Ductile Iron         | 12                     | 2370          | 19.31 | 81.15 | \$ -          | Do Nothing          |
| 327     | WASHINGTON STREET  | AC - Asbestos Cement      | 8                      | 1586          | 29.71 | 0     | \$ 397,166.12 | Small Pipe (Major)  |
| 328     | WESTFIELD DRIVE    | AC - Asbestos Cement      | 10                     | 2425          | 26.52 | 30.72 | \$ -          | Do Nothing          |
| 329     | WINTER STREET      | AC - Asbestos Cement      | 8                      | 2082          | 17.1  | 96.65 | \$ -          | Do Nothing          |
| 33      | DIXON CIRCLE       | AC - Asbestos Cement      | 6                      | 331           | 27.16 | 38.22 | \$ -          | Do Nothing          |
| 330     | FISKE STREET       | AC - Asbestos Cement      | 8                      | 1134          | 53.52 | 0     | \$ 227,185.56 | Small Pipe (Minor)  |
| 331     | FISKE STREET       | AC - Asbestos Cement      | 8                      | 2833          | 53.52 | 0     | \$ 567,563.22 | Small Pipe (Minor)  |
| 332     | WILLOWGATE RISE    | PVC - Poly Vinyl Chloride | 12                     | 1982          | 19.53 | 79.65 | \$ -          | Do Nothing          |
| 333     | HIGHLAND STREET    | AC - Asbestos Cement      | 12                     | 2727          | 26.87 | 28.22 | \$ -          | Do Nothing          |
| 334     | HOLLIS STREET      | AC - Asbestos Cement      | 8                      | 1826          | 30.9  | 0     | \$ 365,820.84 | Small Pipe (Minor)  |
| 335     | UNDERWOOD STREET   | AC - Asbestos Cement      | 8                      | 2026          | 29.37 | 10.73 | \$ -          | Do Nothing          |
| 336     | GORWIN DRIVE       | AC - Asbestos Cement      | 8                      | 2537          | 29.66 | 20.72 | \$ -          | Do Nothing          |
| 337     | MARSHALL STREET    | AC - Asbestos Cement      | 8                      | 1837          | 26.16 | 33.22 | \$ -          | Do Nothing          |
| 338     | HOPPING BROOK ROAD | DI - Ductile Iron         | 10                     | 2737          | 19.17 | 82.15 | \$ -          | Do Nothing          |
| 339     | OLD CART PATH      | DI - Ductile Iron         | 12                     | 3210          | 18.45 | 87.15 | \$ -          | Do Nothing          |
| 34      | DONNA ROAD         | AC - Asbestos Cement      | 6                      | 1449          | 30.9  | 0     | \$ 290,292.66 | Small Pipe (Minor)  |
| 340     | NORFOLK STREET     | ST - Steel                | 8                      | 2024          | 20.43 | 73.29 | \$ -          | Do Nothing          |
| 341     | MARKED TREE ROAD   | AC - Asbestos Cement      | 6                      | 2110          | 29.37 | 10.73 | \$ -          | Do Nothing          |
| 342     | WASHINGTON STREET  | AC - Asbestos Cement      | 8                      | 1633          | 32.62 | 0     | \$ 408,935.86 | Small Pipe (Major)  |
| 343     | WASHINGTON STREET  | AC - Asbestos Cement      | 12                     | 1332          | 30.44 | 3.23  | \$ 400,279.32 | Medium Pipe (Major) |
| 344     | OLD CART PATH      | DI - Ductile Iron         | 12                     | 3513          | 18.45 | 87.15 | \$ -          | Do Nothing          |
| 345     | MARSHALL STREET    | DI - Ductile Iron         | 12                     | 2316          | 18.88 | 84.15 | \$ -          | Do Nothing          |
| 346     | HANLON ROAD        | AC - Asbestos Cement      | 8                      | 416           | 26.16 | 33.22 | \$ -          | Do Nothing          |
| 348     | GORWIN DRIVE       | AC - Asbestos Cement      | 8                      | 398           | 32.71 | 20.72 | \$ -          | Do Nothing          |
| 349     | GORWIN DRIVE       | AC - Asbestos Cement      | 8                      | 232           | 32.52 | 20.72 | \$ -          | Do Nothing          |
| 35      | DORSET ROAD        | AC - Asbestos Cement      | 6                      | 1326          | 28.3  | 18.22 | \$ -          | Do Nothing          |
| 350     | UNDERWOOD STREET   | AC - Asbestos Cement      | 8                      | 913           | 29.37 | 10.73 | \$ -          | Do Nothing          |

| PIPE ID | STREETNAME         | MATERIAL TYPE             | PIPE DIAMETER (INCHES) | LENGTH (FEET) | NPR   | PCI   | REPAIR COST   | REPAIR CATEGORY    |
|---------|--------------------|---------------------------|------------------------|---------------|-------|-------|---------------|--------------------|
| 351     | HOWARD STREET      | AC - Asbestos Cement      | 6                      | 255           | 25.8  | 35.72 | \$ -          | Do Nothing         |
| 352     | HOWARD STREET      | AC - Asbestos Cement      | 6                      | 308           | 25.8  | 35.72 | \$ -          | Do Nothing         |
| 353     | WASHINGTON STREET  | AC - Asbestos Cement      | 8                      | 741           | 58.29 | 0     | \$ 185,561.22 | Small Pipe (Major) |
| 354     | SHAW FARM ROAD     | AC - Asbestos Cement      | 6                      | 114           | 17.1  | 96.65 | \$ -          | Do Nothing         |
| 355     | SHAW FARM ROAD     | AC - Asbestos Cement      | 6                      | 444           | 23.57 | 96.65 | \$ -          | Do Nothing         |
| 356     | APPLEYARD LANE     | AC - Asbestos Cement      | 6                      | 274           | 23.57 | 96.65 | \$ -          | Do Nothing         |
| 357     | WATER STREET       | AC - Asbestos Cement      | 8                      | 486           | 26.87 | 28.22 | \$ -          | Do Nothing         |
| 358     | UNION STREET       | AC - Asbestos Cement      | 8                      | 637           | 24.37 | 45.72 | \$ -          | Do Nothing         |
| 359     | UNION STREET       | AC - Asbestos Cement      | 8                      | 459           | 21.86 | 96.65 | \$ -          | Do Nothing         |
| 36      | DUDLEY ROAD        | AC - Asbestos Cement      | 6                      | 412           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 360     | DAVID STREET       | AC - Asbestos Cement      | 6                      | 183           | 31.28 | 30.72 | \$ -          | Do Nothing         |
| 361     | PRENTICE STREET    | AC - Asbestos Cement      | 8                      | 423           | 29.37 | 10.73 | \$ -          | Do Nothing         |
| 362     | PINECREST ROAD     | AC - Asbestos Cement      | 8                      | 117           | 33.06 | 18.22 | \$ -          | Do Nothing         |
| 363     | HIGHLAND STREET    | AC - Asbestos Cement      | 12                     | 881           | 26.87 | 28.22 | \$ -          | Do Nothing         |
| 364     | HIGHLAND STREET    | AC - Asbestos Cement      | 12                     | 403           | 31.64 | 28.22 | \$ -          | Do Nothing         |
| 365     | CENTRAL STREET     | AC - Asbestos Cement      | 8                      | 418           | 20.58 | 84.29 | \$ -          | Do Nothing         |
| 366     | CENTRAL STREET     | AC - Asbestos Cement      | 8                      | 195           | 18.86 | 84.29 | \$ -          | Do Nothing         |
| 367     | MITCHELL ROAD      | PVC - Poly Vinyl Chloride | 6                      | 725           | 19.31 | 81.15 | \$ -          | Do Nothing         |
| 368     | MITCHELL ROAD      | PVC - Poly Vinyl Chloride | 6                      | 638           | 24.07 | 81.15 | \$ -          | Do Nothing         |
| 369     | FISKE STREET       | AC - Asbestos Cement      | 8                      | 1174          | 55.24 | 0     | \$ 235,199.16 | Small Pipe (Minor) |
| 37      | EVERGREEN ROAD     | AC - Asbestos Cement      | 6                      | 499           | 25.8  | 35.72 | \$ -          | Do Nothing         |
| 370     | FISKE STREET       | AC - Asbestos Cement      | 8                      | 418           | 53.52 | 0     | \$ 83,742.12  | Small Pipe (Minor) |
| 371     | BOGASTOW BOOK ROAD | AC - Asbestos Cement      | 8                      | 227           | 23.11 | 54.58 | \$ -          | Do Nothing         |
| 372     | BOGASTOW BOOK ROAD | AC - Asbestos Cement      | 8                      | 283           | 27.87 | 54.58 | \$ -          | Do Nothing         |
| 373     | MARILYN STREET     | AC - Asbestos Cement      | 6                      | 49            | 31.64 | 28.22 | \$ -          | Do Nothing         |
| 374     | LOWLAND STREET     | AC - Asbestos Cement      | 12                     | 502           | 24.37 | 45.72 | \$ -          | Do Nothing         |
| 375     | LOWLAND STREET     | AC - Asbestos Cement      | 12                     | 782           | 29.14 | 45.72 | \$ -          | Do Nothing         |
| 376     | CURVE STREET       | AC - Asbestos Cement      | 8                      | 309           | 29.85 | 40.72 | \$ -          | Do Nothing         |
| 377     | WINTER STREET      | AC - Asbestos Cement      | 8                      | 572           | 17.1  | 96.65 | \$ -          | Do Nothing         |
| 378     | WINTER STREET      | AC - Asbestos Cement      | 8                      | 195           | 21.86 | 96.65 | \$ -          | Do Nothing         |
| 379     | WINTER STREET      | AC - Asbestos Cement      | 8                      | 569           | 21.86 | 96.65 | \$ -          | Do Nothing         |
| 38      | FAIRLANE WAY       | AC - Asbestos Cement      | 6                      | 1112          | 29.66 | 20.72 | \$ -          | Do Nothing         |
| 380     | WESTFIELD DRIVE    | AC - Asbestos Cement      | 10                     | 713           | 26.52 | 30.72 | \$ -          | Do Nothing         |
| 381     | WESTFIELD DRIVE    | AC - Asbestos Cement      | 10                     | 282           | 31.28 | 30.72 | \$ -          | Do Nothing         |
| 382     | JAR BROOK ROAD     | AC - Asbestos Cement      | 6                      | 74            | 34.13 | 10.73 | \$ -          | Do Nothing         |
| 383     | WASHINGTON STREET  | AC - Asbestos Cement      | 6                      | 520           | 32.71 | 20.72 | \$ -          | Do Nothing         |
| 384     | CRANBERRY LANE     | AC - Asbestos Cement      | 6                      | 27            | 30.92 | 33.22 | \$ -          | Do Nothing         |
| 385     | CONCORD STREET     | DI - Ductile Iron         | 12                     | 1399          | 28.65 | 81.15 | \$ -          | Do Nothing         |
| 386     | TURNER ROAD        | AC - Asbestos Cement      | 6                      | 211           | 34.85 | 5.73  | \$ -          | Do Nothing         |
| 387     | WINTER STREET      | AC - Asbestos Cement      | 6                      | 453           | 23.57 | 96.65 | \$ -          | Do Nothing         |
| 388     | WINTER STREET      | AC - Asbestos Cement      | 6                      | 860           | 21.67 | 96.65 | \$ -          | Do Nothing         |
| 389     | DORSET ROAD        | AC - Asbestos Cement      | 6                      | 334           | 30.02 | 18.22 | \$ -          | Do Nothing         |
| 39      | FISHER STREET      | AC - Asbestos Cement      | 6                      | 792           | 26.52 | 30.72 | \$ -          | Do Nothing         |
| 390     | DORSET ROAD        | AC - Asbestos Cement      | 6                      | 178           | 34.78 | 18.22 | \$ -          | Do Nothing         |
| 391     | ADAM WHEELER LANE  | AC - Asbestos Cement      | 6                      | 591           | 32.71 | 20.72 | \$ -          | Do Nothing         |
| 392     | NORFOLK STREET     | AC - Asbestos Cement      | 8                      | 327           | 29.66 | 20.72 | \$ -          | Do Nothing         |
| 393     | NORFOLK STREET     | AC - Asbestos Cement      | 8                      | 391           | 32.71 | 20.72 | \$ -          | Do Nothing         |
| 394     | LAKE SHORE DRIVE   | AC - Asbestos Cement      | 6                      | 103           | 28.78 | 48.22 | \$ -          | Do Nothing         |
| 395     | SUMMER STREET      | AC - Asbestos Cement      | 8                      | 799           | 30.9  | 0     | \$ 200,085.58 | Small Pipe (Major) |
| 396     | SUMMER STREET      | AC - Asbestos Cement      | 8                      | 335           | 35.67 | 0     | \$ 83,890.70  | Small Pipe (Major) |
| 397     | WASHINGTON STREET  | AC - Asbestos Cement      | 8                      | 482           | 53.52 | 0     | \$ 120,702.44 | Small Pipe (Major) |
| 398     | WASHINGTON STREET  | AC - Asbestos Cement      | 8                      | 545           | 53.52 | 0     | \$ 136,478.90 | Small Pipe (Major) |
| 399     | WASHINGTON STREET  | AC - Asbestos Cement      | 8                      | 250           | 58.29 | 0     | \$ 62,605.00  | Small Pipe (Major) |
| 40      | GREEN STREET       | AC - Asbestos Cement      | 6                      | 737           | 28.23 | 30.72 | \$ -          | Do Nothing         |



| PIPE ID | STREETNAME        | MATERIAL TYPE             | PIPE DIAMETER (INCHES) | LENGTH (FEET) | NPR   | PCI   | REPAIR COST   | REPAIR CATEGORY    |
|---------|-------------------|---------------------------|------------------------|---------------|-------|-------|---------------|--------------------|
| 400     | WASHINGTON STREET | AC - Asbestos Cement      | 8                      | 314           | 58.29 | 0     | \$ 78,631.88  | Small Pipe (Major) |
| 401     | SOUTH STREET      | AC - Asbestos Cement      | 6                      | 582           | 28.16 | 52.58 | \$ -          | Do Nothing         |
| 402     | ADAMS STREET      | AC - Asbestos Cement      | 8                      | 77            | 32.35 | 23.22 | \$ -          | Do Nothing         |
| 403     | ADAMS STREET      | AC - Asbestos Cement      | 8                      | 873           | 32.35 | 23.22 | \$ -          | Do Nothing         |
| 404     | MARSHALL STREET   | AC - Asbestos Cement      | 8                      | 271           | 26.16 | 33.22 | \$ -          | Do Nothing         |
| 405     | ADAMS STREET      | AC - Asbestos Cement      | 8                      | 304           | 27.59 | 23.22 | \$ -          | Do Nothing         |
| 406     | GORWIN DRIVE      | AC - Asbestos Cement      | 8                      | 325           | 30.92 | 33.22 | \$ -          | Do Nothing         |
| 407     | ADAMS STREET      | AC - Asbestos Cement      | 8                      | 196           | 32.35 | 23.22 | \$ -          | Do Nothing         |
| 408     | ADAMS STREET      | AC - Asbestos Cement      | 8                      | 1031          | 27.59 | 23.22 | \$ -          | Do Nothing         |
| 409     | ADAMS STREET      | AC - Asbestos Cement      | 8                      | 100           | 32.35 | 23.22 | \$ -          | Do Nothing         |
| 41      | GREENVIEW DRIVE   | AC - Asbestos Cement      | 6                      | 81            | 28.16 | 52.58 | \$ -          | Do Nothing         |
| 410     | ADAMS STREET      | AC - Asbestos Cement      | 8                      | 1063          | 34.06 | 23.22 | \$ -          | Do Nothing         |
| 411     | GORWIN DRIVE      | AC - Asbestos Cement      | 8                      | 310           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 412     | GORWIN DRIVE      | AC - Asbestos Cement      | 8                      | 738           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 413     | OAK STREET        | AC - Asbestos Cement      | 6                      | 751           | 35.21 | 3.23  | \$ 150,455.34 | Small Pipe (Minor) |
| 414     | NORTH MILL STREET | AC - Asbestos Cement      | 8                      | 215           | 29.85 | 40.72 | \$ -          | Do Nothing         |
| 415     | NORTH MILL STREET | AC - Asbestos Cement      | 8                      | 263           | 25.09 | 40.72 | \$ -          | Do Nothing         |
| 416     | NORTH MILL STREET | AC - Asbestos Cement      | 8                      | 485           | 25.09 | 40.72 | \$ -          | Do Nothing         |
| 417     | HARGRAVE AVENUE   | AC - Asbestos Cement      | 8                      | 72            | 29.85 | 40.72 | \$ -          | Do Nothing         |
| 418     | MILL STREET       | AC - Asbestos Cement      | 8                      | 619           | 24.37 | 45.72 | \$ -          | Do Nothing         |
| 419     | MILL STREET       | AC - Asbestos Cement      | 8                      | 712           | 29.14 | 45.72 | \$ -          | Do Nothing         |
| 42      | GREENVIEW DRIVE   | AC - Asbestos Cement      | 6                      | 937           | 24.37 | 45.72 | \$ -          | Do Nothing         |
| 420     | FISKE STREET      | AC - Asbestos Cement      | 8                      | 267           | 53.52 | 0     | \$ 53,490.78  | Small Pipe (Minor) |
| 421     | FISKE STREET      | AC - Asbestos Cement      | 8                      | 446           | 58.29 | 0     | \$ 89,351.64  | Small Pipe (Minor) |
| 422     | FISKE STREET      | AC - Asbestos Cement      | 8                      | 261           | 58.29 | 0     | \$ 52,288.74  | Small Pipe (Minor) |
| 423     | WINTER STREET     | AC - Asbestos Cement      | 8                      | 1027          | 17.1  | 96.65 | \$ -          | Do Nothing         |
| 424     | WINTER STREET     | AC - Asbestos Cement      | 8                      | 351           | 21.86 | 96.65 | \$ -          | Do Nothing         |
| 425     | WASHINGTON STREET | AC - Asbestos Cement      | 8                      | 1304          | 55.24 | 0     | \$ 326,547.68 | Small Pipe (Major) |
| 426     | WASHINGTON STREET | AC - Asbestos Cement      | 8                      | 547           | 53.52 | 0     | \$ 136,979.74 | Small Pipe (Major) |
| 427     | WASHINGTON STREET | AC - Asbestos Cement      | 8                      | 956           | 53.52 | 0     | \$ 239,401.52 | Small Pipe (Major) |
| 428     | WASHINGTON STREET | AC - Asbestos Cement      | 8                      | 558           | 53.52 | 0     | \$ 139,734.36 | Small Pipe (Major) |
| 429     | DEAN ROAD         | AC - Asbestos Cement      | 6                      | 313           | 30.44 | 3.23  | \$ 62,706.42  | Small Pipe (Minor) |
| 43      | GREENVIEW DRIVE   | AC - Asbestos Cement      | 6                      | 371           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 430     | DEAN ROAD         | AC - Asbestos Cement      | 6                      | 383           | 35.21 | 3.23  | \$ 76,730.22  | Small Pipe (Minor) |
| 431     | TRAVIS ROAD       | AC - Asbestos Cement      | 6                      | 179           | 26.16 | 33.22 | \$ -          | Do Nothing         |
| 432     | TRAVIS ROAD       | AC - Asbestos Cement      | 6                      | 300           | 30.92 | 33.22 | \$ -          | Do Nothing         |
| 433     | HOLLIS STREET     | AC - Asbestos Cement      | 8                      | 279           | 30.9  | 0     | \$ 55,894.86  | Small Pipe (Minor) |
| 434     | HOLLIS STREET     | AC - Asbestos Cement      | 8                      | 271           | 37.38 | 0     | \$ 54,292.14  | Small Pipe (Minor) |
| 435     | ASHLAND STREET    | AC - Asbestos Cement      | 6                      | 2263          | 37.38 | 0     | \$ 453,369.42 | Small Pipe (Minor) |
| 436     | HIGHLAND STREET   | DI - Ductile Iron         | 12                     | 2302          | 17.95 | 90.65 | \$ -          | Do Nothing         |
| 44      | GREGORY ROAD      | AC - Asbestos Cement      | 6                      | 1407          | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 45      | GROVE STREET      | AC - Asbestos Cement      | 6                      | 595           | 24.37 | 45.72 | \$ -          | Do Nothing         |
| 46      | HAMPSHIRE STREET  | AC - Asbestos Cement      | 6                      | 506           | 24.37 | 45.72 | \$ -          | Do Nothing         |
| 47      | HEMLOCK DRIVE     | AC - Asbestos Cement      | 6                      | 1877          | 29.66 | 20.72 | \$ -          | Do Nothing         |
| 48      | HERITAGE WAY      | AC - Asbestos Cement      | 6                      | 523           | 21.67 | 96.65 | \$ -          | Do Nothing         |
| 49      | HIGH ROCK ROAD    | AC - Asbestos Cement      | 6                      | 940           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 5       | WILSON STREET     | PVC - Poly Vinyl Chloride | 2                      | 715           | 58.29 | 0     | \$ 143,243.10 | Small Pipe (Minor) |
| 50      | HIGH STREET       | AC - Asbestos Cement      | 6                      | 2360          | 40.24 | 0     | \$ 590,991.20 | Small Pipe (Major) |
| 51      | HOLLY LANE        | AC - Asbestos Cement      | 6                      | 2330          | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 52      | HOWARD STREET     | AC - Asbestos Cement      | 6                      | 407           | 25.8  | 35.72 | \$ -          | Do Nothing         |
| 53      | INDIAN RIDGE      | PVC - Poly Vinyl Chloride | 6                      | 557           | 18.38 | 87.65 | \$ -          | Do Nothing         |
| 54      | JAR BROOK ROAD    | AC - Asbestos Cement      | 6                      | 870           | 31.09 | 10.73 | \$ -          | Do Nothing         |
| 55      | JERROLD STREET    | AC - Asbestos Cement      | 6                      | 2788          | 29.66 | 20.72 | \$ -          | Do Nothing         |
| 56      | JAMES             | AC - Asbestos Cement      | 6                      | 993           | 30.9  | 0     | \$ 198,937.62 | Small Pipe (Minor) |

| PIPE ID | STREETNAME        | MATERIAL TYPE             | PIPE DIAMETER (INCHES) | LENGTH (FEET) | NPR   | PCI   | REPAIR COST   | REPAIR CATEGORY    |
|---------|-------------------|---------------------------|------------------------|---------------|-------|-------|---------------|--------------------|
| 57      | LAKE SHORE DRIVE  | AC - Asbestos Cement      | 6                      | 1271          | 24.02 | 48.22 | \$ -          | Do Nothing         |
| 58      | LINDEN STREET     | DI - Ductile Iron         | 12                     | 102           | 21.39 | 66.58 | \$ -          | Do Nothing         |
| 59      | LOCUST STREET     | AC - Asbestos Cement      | 6                      | 2934          | 32.62 | 0     | \$ 587,797.56 | Small Pipe (Minor) |
| 6       | WINTHROP STREET   | AC - Asbestos Cement      | 2                      | 240           | 46.38 | 0     | \$ 48,081.60  | Small Pipe (Minor) |
| 60      | LOUIS STREET      | AC - Asbestos Cement      | 6                      | 885           | 25.8  | 35.72 | \$ -          | Do Nothing         |
| 61      | MARILYN STREET    | AC - Asbestos Cement      | 6                      | 1857          | 26.87 | 28.22 | \$ -          | Do Nothing         |
| 62      | MARKED TREE ROAD  | AC - Asbestos Cement      | 6                      | 2190          | 29.37 | 10.73 | \$ -          | Do Nothing         |
| 63      | MEADOWBROOK LANE  | AC - Asbestos Cement      | 6                      | 2106          | 30.21 | 38.22 | \$ -          | Do Nothing         |
| 64      | MILL STREET       | AC - Asbestos Cement      | 6                      | 1100          | 22.54 | 58.58 | \$ -          | Do Nothing         |
| 65      | MITCHELL ROAD     | PVC - Poly Vinyl Chloride | 6                      | 660           | 19.31 | 81.15 | \$ -          | Do Nothing         |
| 66      | MORSE FARM ROAD   | PVC - Poly Vinyl Chloride | 6                      | 479           | 19.38 | 80.65 | \$ -          | Do Nothing         |
| 67      | MORTON STREET     | AC - Asbestos Cement      | 6                      | 945           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 68      | NORFOLK STREET    | AC - Asbestos Cement      | 6                      | 1023          | 30.8  | 0.73  | \$ 204,947.82 | Small Pipe (Minor) |
| 69      | NORTHWAY STREET   | AC - Asbestos Cement      | 6                      | 1207          | 29.66 | 20.72 | \$ -          | Do Nothing         |
| 70      | OAK STREET        | AC - Asbestos Cement      | 6                      | 1393          | 30.44 | 3.23  | \$ 279,073.62 | Small Pipe (Minor) |
| 71      | OAKHURST LANE     | AC - Asbestos Cement      | 6                      | 538           | 30.9  | 0     | \$ 107,782.92 | Small Pipe (Minor) |
| 72      | ORCHARD LANE      | AC - Asbestos Cement      | 6                      | 808           | 30.56 | 35.72 | \$ -          | Do Nothing         |
| 73      | PEARL STREET      | AC - Asbestos Cement      | 6                      | 1278          | 34.42 | 20.72 | \$ -          | Do Nothing         |
| 74      | PERSIS PLACE      | AC - Asbestos Cement      | 6                      | 234           | 28.3  | 18.22 | \$ -          | Do Nothing         |
| 75      | PETER STREET      | AC - Asbestos Cement      | 6                      | 529           | 29.49 | 43.22 | \$ -          | Do Nothing         |
| 76      | PINE STREET       | AC - Asbestos Cement      | 6                      | 457           | 27.16 | 38.22 | \$ -          | Do Nothing         |
| 77      | PLEASANT STREET   | AC - Asbestos Cement      | 6                      | 226           | 17.1  | 96.65 | \$ -          | Do Nothing         |
| 78      | POPE ROAD         | AC - Asbestos Cement      | 6                      | 1124          | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 79      | PROSPECT STREET   | AC - Asbestos Cement      | 6                      | 3019          | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 80      | PETER STREET      | AC - Asbestos Cement      | 6                      | 849           | 25.8  | 35.72 | \$ -          | Do Nothing         |
| 81      | QUAIL RUN         | DI - Ductile Iron         | 6                      | 405           | 18.88 | 84.15 | \$ -          | Do Nothing         |
| 82      | QUINCY PLACE      | AC - Asbestos Cement      | 6                      | 418           | 26.82 | 60.58 | \$ -          | Do Nothing         |
| 83      | RICH ROAD         | AC - Asbestos Cement      | 6                      | 214           | 30.9  | 0     | \$ 42,872.76  | Small Pipe (Minor) |
| 84      | RIDGE ROAD        | AC - Asbestos Cement      | 6                      | 999           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 85      | ROBERT ROAD       | AC - Asbestos Cement      | 6                      | 2018          | 37.28 | 20.72 | \$ -          | Do Nothing         |
| 86      | ROCKLAND STREET   | AC - Asbestos Cement      | 6                      | 1733          | 30.8  | 0.73  | \$ 347,189.22 | Small Pipe (Minor) |
| 87      | ROY AVENUE        | AC - Asbestos Cement      | 6                      | 1417          | 28.23 | 30.72 | \$ -          | Do Nothing         |
| 88      | SCHOOL STREET     | AC - Asbestos Cement      | 6                      | 323           | 17.1  | 96.65 | \$ -          | Do Nothing         |
| 89      | SHAW FARM ROAD    | AC - Asbestos Cement      | 6                      | 1191          | 18.81 | 96.65 | \$ -          | Do Nothing         |
| 9       | ADAM WHEELER LANE | AC - Asbestos Cement      | 6                      | 905           | 29.66 | 20.72 | \$ -          | Do Nothing         |
| 90      | SILVER LANE       | AC - Asbestos Cement      | 6                      | 1014          | 27.87 | 33.22 | \$ -          | Do Nothing         |
| 91      | SKYVIEW TERRACE   | AC - Asbestos Cement      | 6                      | 1548          | 32.4  | 1.55  | \$ 310,126.32 | Small Pipe (Minor) |
| 92      | SMITHURST DRIVE   | AC - Asbestos Cement      | 6                      | 495           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 93      | SOUTH STREET      | AC - Asbestos Cement      | 6                      | 720           | 25.11 | 52.58 | \$ -          | Do Nothing         |
| 94      | SPARROW LANE      | AC - Asbestos Cement      | 6                      | 443           | 28.66 | 15.72 | \$ -          | Do Nothing         |
| 95      | SPRUCE STREET     | AC - Asbestos Cement      | 6                      | 518           | 28.66 | 15.72 | \$ -          | Do Nothing         |
| 96      | STAGECOACH ROAD   | AC - Asbestos Cement      | 6                      | 2116          | 32.52 | 20.72 | \$ -          | Do Nothing         |
| 97      | SWEET GRASS LANE  | AC - Asbestos Cement      | 6                      | 959           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 98      | SMITHURST DRIVE   | AC - Asbestos Cement      | 6                      | 340           | 27.94 | 20.72 | \$ -          | Do Nothing         |
| 99      | TAYLOR ROAD       | AC - Asbestos Cement      | 6                      | 511           | 30.9  | 0     | \$ 102,373.74 | Small Pipe (Minor) |



## Appendix B. Priority Project List



| Project  | Plan Year         | Street             | Install Year | Diameter (in)        | Material                  | Length (ft)   | Cost (\$)           |
|--|-------------------|--------------------|--------------|----------------------|---------------------------|---------------|---------------------|
| FISKE, BULLARD, CENTRAL EXPANSION & LOOP                   | 1                 | CENTRAL STREET     | -            | 8                    |                           | 1,450         | \$ 435,000          |
|  | 1                 | FISKE STREET       | 1974         | 8                    | AC - Asbestos Cement      | 1,158         | \$ 347,400          |
|  | 1                 | FISKE STREET       | 1974         | 8                    | AC - Asbestos Cement      | 418           | \$ 125,400          |
|  |                   |                    |              |                      |                           | <b>3,026</b>  | <b>\$ 907,800</b>   |
| FISKE, BULLARD, CENTRAL EXPANSION & LOOP                   | 2                 | BULLARD STREET     | -            | 8                    |                           | 3,090         | \$ 927,000          |
|  |                   |                    |              |                      |                           |               | <b>3,090</b>        |
| NORFOLK STREET (coordinate w/ sidewalk work)               | 3                 | NORFOLK STREET     | 1975         | 8                    | ST - Steel                | 2,384         | \$ 476,800          |
|  | 3                 | NORFOLK STREET     | 1975         | 8                    | ST - Steel                | 2,024         | \$ 404,800          |
|  | 3                 | NORFOLK STREET     | 1966         | 10                   | AC - Asbestos Cement      | 1,377         | \$ 344,250          |
|  |                   |                    |              |                      |                           | <b>5,785</b>  | <b>\$ 1,225,850</b> |
| NORFOLK STREET (coordinate w/ sidewalk work)               | 4                 | NORFOLK STREET     | 1960         | 8                    | AC - Asbestos Cement      | 1,445         | \$ 289,000          |
|  | 4                 | NORFOLK STREET     | 1960         | 8                    | AC - Asbestos Cement      | 327           | \$ 65,400           |
|  | 4                 | NORFOLK STREET     | 1960         | 8                    | AC - Asbestos Cement      | 391           | \$ 78,200           |
|  | 4                 | NORFOLK STREET     | 1952         | 6                    | AC - Asbestos Cement      | 1,023         | \$ 204,600          |
|  |                   |                    |              |                      |                           | <b>3,186</b>  | <b>\$ 637,200</b>   |
| GOULDING STREET NEIGHBORHOOD (coordinate w/ sidewalk work) | 5                 | GOULDING PLACE     | 2005         | 6                    | PVC - Poly Vinyl Chloride | 590           | \$ 118,000          |
|  | 5                 | ALDEN ROAD         | 1960         | 6                    | AC - Asbestos Cement      | 1,140         | \$ 228,000          |
|  | 5                 | DUDLEY ROAD        | 1960         | 6                    | AC - Asbestos Cement      | 412           | \$ 82,400           |
|  | 5                 | GREGORY ROAD       | 1960         | 6                    | AC - Asbestos Cement      | 1,407         | \$ 281,400          |
|  | 5                 | GOULDING STREET    | 1960         | 8                    | AC - Asbestos Cement      | 2,299         | \$ 574,750          |
|  |                   |                    |              |                      |                           | <b>5,848</b>  | <b>\$ 1,284,550</b> |
| GOULDING STREET NEIGHBORHOOD (coordinate w/ sidewalk work) | 6                 | TRACY LYN ROAD     | 1964         | 6                    | AC - Asbestos Cement      | 1,116         | \$ 223,200          |
|  | 6                 | ADAM WHEELER LANE  | 1960         | 6                    | AC - Asbestos Cement      | 905           | \$ 181,000          |
|  | 6                 | BRADFORD JAY ROAD  | 1960         | 6                    | AC - Asbestos Cement      | 1,002         | \$ 200,400          |
|  | 6                 | HIGH ROCK ROAD     | 1960         | 6                    | AC - Asbestos Cement      | 940           | \$ 188,000          |
|  | 6                 | HOLLY LANE         | 1960         | 6                    | AC - Asbestos Cement      | 2,330         | \$ 466,000          |
|  | 6                 | SWEET GRASS LANE   | 1960         | 6                    | AC - Asbestos Cement      | 959           | \$ 191,800          |
| 6  | ADAM WHEELER LANE | 1960               | 6            | AC - Asbestos Cement | 591                       | \$ 118,200    |                     |
|  |                   |                    |              |                      |                           | <b>7,843</b>  | <b>\$ 1,568,600</b> |
| CENTRAL STREET   | 7                 | CENTRAL STREET     | 1996         | 8                    | AC - Asbestos Cement      | 641           | \$ 128,200          |
|  | 7                 | CENTRAL STREET     | 1996         | 8                    | AC - Asbestos Cement      | 418           | \$ 83,600           |
|  | 7                 | CENTRAL STREET     | 1996         | 8                    | AC - Asbestos Cement      | 195           | \$ 39,000           |
|  | 7                 | CENTRAL STREET     | 1972         | 8                    | AC - Asbestos Cement      | 3818          | \$ 763,600          |
|  | 7                 | CENTRAL STREET     | 1972         | 12                   | AC - Asbestos Cement      | 1491          | \$ 372,750          |
|  | 7                 | CENTRAL STREET     | 1970         | 8                    | AC - Asbestos Cement      | 2570          | \$ 514,000          |
|  | 7                 | CENTRAL STREET     | 1946         | 6                    | AC - Asbestos Cement      | 1024          | \$ 204,800          |
|  |                   |                    |              |                      |                           | <b>10,157</b> | <b>\$ 2,105,950</b> |
| CONCORD STREET   | 8                 | CONCORD STREET     | 1953         | 12                   | AC - Asbestos Cement      | 3761          | \$ 1,128,300        |
|  | 8                 | CONCORD STREET     | 1949         | 8                    | AC - Asbestos Cement      | 1702          | \$ 425,500          |
|  |                   |                    |              |                      |                           | <b>5,463</b>  | <b>\$ 1,553,800</b> |
| WASHINGTON STREET DOUBLE WATER MAIN                        | 9                 | WASHINGTON STREET  | 1953         | 8                    | AC - Asbestos Cement      | 76            | \$ 16,880           |
|  | 9                 | WASHINGTON STREET  | 1953         | 8                    | AC - Asbestos Cement      | 613           | \$ 153,250          |
|  | 9                 | WASHINGTON STREET  | 1953         | 12                   | AC - Asbestos Cement      | 2310          | \$ 693,000          |
|  | 9                 | WASHINGTON STREET  | 1953         | 12                   | AC - Asbestos Cement      | 1332          | \$ 399,600          |
|  | 9                 | WASHINGTON STREET  | 1900         | 8                    | AC - Asbestos Cement      | 1586          | \$ 396,500          |
|  | 9                 | WASHINGTON STREET  | 1900         | 8                    | AC - Asbestos Cement      | 1633          | \$ 489,900          |
|  |                   |                    |              |                      |                           | <b>7,550</b>  | <b>\$ 2,149,130</b> |
| HOLLIS STREET  | 10                | HOLLIS STREET      | 1949         | 8                    | AC - Asbestos Cement      | 2812          | \$ 562,400          |
|  | 10                | HOLLIS STREET      | 1949         | 8                    | AC - Asbestos Cement      | 1826          | \$ 365,200          |
|  | 10                | HOLLIS STREET      | 1949         | 8                    | AC - Asbestos Cement      | 279           | \$ 55,800           |
|  | 10                | HOLLIS STREET      | 1949         | 8                    | AC - Asbestos Cement      | 271           | \$ 54,200           |
|  |                   |                    |              |                      |                           | <b>5,188</b>  | <b>\$ 1,037,600</b> |
| PRENTICE STREET  | 11                | PRENTICE STREET    | -            | 8                    |                           | 3586          | \$ 717,200          |
|  |                   |                    |              |                      |                           | <b>3,586</b>  | <b>\$ 717,200</b>   |
| CHAMBERLAIN STREET   | 12                | CHAMBERLAIN STREET | -            | 8                    |                           | 2592          | \$ 518,400          |
|  |                   |                    |              |                      |                           | <b>2,592</b>  | <b>\$ 518,400</b>   |
| HIGH STREET  | 13                | WASHINGTON STREET  | 1953         | 10                   | AC - Asbestos Cement      | 2304          | \$ 691,200          |
|  | 13                | WASHINGTON STREET  | 1953         | 12                   | AC - Asbestos Cement      | 603           | \$ 180,900          |
|  | 13                | HIGH STREET        | 1949         | 6                    | AC - Asbestos Cement      | 2360          | \$ 590,000          |
|  | 13                | HIGH STREET        | 1949         | 8                    | AC - Asbestos Cement      | 2030          | \$ 507,500          |
|  | 13                | WASHINGTON STREET  | 1949         | 10                   | AC - Asbestos Cement      | 1771          | \$ 531,300          |
|  |                   |                    |              |                      |                           | <b>9,068</b>  | <b>\$ 2,500,900</b> |
| WOODLAND STREET  | 14                | WOODLAND STREET    | 1985         | 12                   | DI - Ductile Iron         | 4400          | \$ 1,320,000        |
|  |                   |                    |              |                      |                           | <b>4,400</b>  | <b>\$ 1,320,000</b> |
| CABOT ROAD NEIGHBORHOOD                                    | 15                | CABOT ROAD         | 1975         | 6                    | AC - Asbestos Cement      | 934           | \$ 186,800          |
|  | 15                | COTTAGE DRIVE      | 1975         | 6                    | AC - Asbestos Cement      | 916           | \$ 183,200          |
|  | 15                | BIRCH ROAD         | 1971         | 6                    | AC - Asbestos Cement      | 934           | \$ 186,800          |
|  | 15                | LAKE SHORE DRIVE   | 1971         | 6                    | AC - Asbestos Cement      | 1271          | \$ 254,200          |
|  | 15                | LAKE SHORE DRIVE   | 1971         | 6                    | AC - Asbestos Cement      | 103           | \$ 20,600           |
|  | 15                | CEDAR ROAD         | 1953         | 8                    | AC - Asbestos Cement      | 462           | \$ 92,400           |
|  |                   |                    |              |                      |                           | <b>4,620</b>  | <b>\$ 924,000</b>   |

Appendix B. Priority Project List



| Project                 | Plan Year | Street             | Install Year | Diameter (in) | Material                  | Length (ft)    | Cost (\$)            |
|-------------------------|-----------|--------------------|--------------|---------------|---------------------------|----------------|----------------------|
| OAK STREET NEIGHBORHOOD | 16        | WALNUT ROAD        | 1976         | 6             | AC - Asbestos Cement      | 571            | \$ 114,200           |
|                         | 16        | EVERGREEN ROAD     | 1966         | 6             | AC - Asbestos Cement      | 499            | \$ 99,800            |
|                         | 16        | HEMLOCK DRIVE      | 1960         | 6             | AC - Asbestos Cement      | 1877           | \$ 375,400           |
|                         | 16        | OAK STREET         | 1959         | 8             | AC - Asbestos Cement      | 1490           | \$ 298,000           |
|                         | 16        | OAK STREET         | 1953         | 6             | AC - Asbestos Cement      | 1393           | \$ 278,600           |
|                         | 16        | OAK STREET         | 1953         | 6             | AC - Asbestos Cement      | 751            | \$ 150,200           |
|                         |           |                    |              |               |                           | <b>6,581</b>   | <b>\$ 1,316,200</b>  |
| WASHINGTON STREET       | 17        | WASHINGTON STREET  | 1950         | 8             | AC - Asbestos Cement      | 841            | \$ 210,603           |
|                         | 17        | WASHINGTON STREET  | 1950         | 8             | AC - Asbestos Cement      | 598            | \$ 149,751           |
|                         | 17        | WASHINGTON STREET  | 1950         | 8             | AC - Asbestos Cement      | 741            | \$ 185,561           |
|                         | 17        | WASHINGTON STREET  | 1950         | 8             | AC - Asbestos Cement      | 1304           | \$ 349,798           |
|                         | 17        | WASHINGTON STREET  | 1950         | 8             | AC - Asbestos Cement      | 547            | \$ 151,864           |
|                         | 17        | WASHINGTON STREET  | 1950         | 8             | AC - Asbestos Cement      | 956            | \$ 265,414           |
|                         |           |                    |              |               |                           | <b>4,987</b>   | <b>\$ 1,312,991</b>  |
| WASHINGTON STREET       | 18        | WASHINGTON STREET  | 1950         | 8             | AC - Asbestos Cement      | 807            | \$ 202,089           |
|                         | 18        | WASHINGTON STREET  | 1950         | 8             | AC - Asbestos Cement      | 482            | \$ 133,818           |
|                         | 18        | WASHINGTON STREET  | 1950         | 8             | AC - Asbestos Cement      | 545            | \$ 151,308           |
|                         | 18        | WASHINGTON STREET  | 1950         | 8             | AC - Asbestos Cement      | 250            | \$ 62,605            |
|                         | 18        | WASHINGTON STREET  | 1950         | 8             | AC - Asbestos Cement      | 314            | \$ 78,632            |
|                         | 18        | WASHINGTON STREET  | 1950         | 8             | AC - Asbestos Cement      | 558            | \$ 154,918           |
|                         |           |                    |              |               |                           | <b>2,956</b>   | <b>\$ 783,369</b>    |
| FISKE STREET            | 19        | FISKE STREET       | 1974         | 8             | AC - Asbestos Cement      | 1134           | \$ 243,356           |
|                         | 19        | FISKE STREET       | 1974         | 8             | AC - Asbestos Cement      | 2833           | \$ 607,962           |
|                         | 19        | FISKE STREET       | 1974         | 8             | AC - Asbestos Cement      | 267            | \$ 55,362            |
|                         | 19        | FISKE STREET       | 1974         | 8             | AC - Asbestos Cement      | 446            | \$ 89,352            |
|                         | 19        | WASHINGTON STREET  | 1950         | 8             | AC - Asbestos Cement      | 2873           | \$ 744,624           |
|                         |           |                    |              |               |                           | <b>7,553</b>   | <b>\$ 1,740,656</b>  |
| SUMMER STREET           | 20        | FISKE STREET       | 1974         | 8             | AC - Asbestos Cement      | 1174           | \$ 243,429           |
|                         | 20        | FISKE STREET       | 1974         | 8             | AC - Asbestos Cement      | 261            | \$ 52,289            |
|                         | 20        | SUMMER STREET      | 1949         | 8             | AC - Asbestos Cement      | 1859           | \$ 465,531           |
|                         | 20        | SUMMER STREET      | 1949         | 8             | AC - Asbestos Cement      | 799            | \$ 200,086           |
|                         | 20        | SUMMER STREET      | 1949         | 8             | AC - Asbestos Cement      | 335            | \$ 96,269            |
|                         |           |                    |              |               |                           | <b>4,428</b>   | <b>\$ 1,057,603</b>  |
| ASHLAND STREET          | 21        | ASHLAND STREET     | 1949         | 6             | AC - Asbestos Cement      | 2428           | \$ 486,426           |
|                         | 21        | LOCUST STREET      | 1949         | 6             | AC - Asbestos Cement      | 2934           | \$ 587,798           |
|                         | 21        | ASHLAND STREET     | 1949         | 8             | AC - Asbestos Cement      | 278            | \$ 66,145            |
|                         | 21        | ASHLAND STREET     | 1949         | 12            | AC - Asbestos Cement      | 696            | \$ 193,230           |
|                         | 21        | ASHLAND STREET     | 1949         | 6             | AC - Asbestos Cement      | 2263           | \$ 453,369           |
|                         |           |                    |              |               |                           | <b>8,599</b>   | <b>\$ 1,786,968</b>  |
| MITCHELL ROAD           | 22        | BEVERLY CIRCLE     | 1987         | 8             | PVC - Poly Vinyl Chloride | 417            | \$ 83,400            |
|                         | 22        | BYRON ROAD         | 1986         | 6             | PVC - Poly Vinyl Chloride | 422            | \$ 84,400            |
|                         | 22        | MITCHELL ROAD      | 1984         | 6             | PVC - Poly Vinyl Chloride | 660            | \$ 132,000           |
|                         | 22        | MITCHELL ROAD      | 1984         | 6             | PVC - Poly Vinyl Chloride | 725            | \$ 145,000           |
|                         | 22        | MITCHELL ROAD      | 1984         | 6             | PVC - Poly Vinyl Chloride | 638            | \$ 127,600           |
|                         | 22        | SKYVIEW TERRACE    | 1952         | 6             | AC - Asbestos Cement      | 1548           | \$ 310,126           |
|                         | 22        | DONNA ROAD         | 1951         | 6             | AC - Asbestos Cement      | 1449           | \$ 290,293           |
|                         | 22        | RICH ROAD          | 1950         | 6             | AC - Asbestos Cement      | 214            | \$ 42,873            |
|                         |           |                    |              |               |                           | <b>6,073</b>   | <b>\$ 1,215,692</b>  |
| ROCKLAND STREET         | 23        | WASHINGTON STREET  | 1953         | 8             | AC - Asbestos Cement      | 3183           | \$ 797,087           |
|                         | 23        | ROCKLAND STREET    | 1952         | 6             | AC - Asbestos Cement      | 606            | \$ 121,406           |
|                         | 23        | ROCKLAND STREET    | 1952         | 6             | AC - Asbestos Cement      | 1733           | \$ 347,189           |
|                         |           |                    |              |               |                           | <b>5,522</b>   | <b>\$ 1,265,682</b>  |
| UNDERWOOD STREET        | 24        | UNDERWOOD STREET   | 1956         | 8             | AC - Asbestos Cement      | 1490           | \$ 372,500           |
|                         | 24        | UNDERWOOD STREET   | 1956         | 8             | AC - Asbestos Cement      | 2026           | \$ 506,500           |
|                         | 24        | UNDERWOOD STREET   | 1956         | 8             | AC - Asbestos Cement      | 913            | \$ 228,250           |
|                         |           |                    |              |               |                           | <b>4,429</b>   | <b>\$ 1,107,250</b>  |
| CHAMBERLAIN STREET      | 25        | ANDREW LANE        | 1960         | 8             | AC - Asbestos Cement      | 1362           | \$ 272,400           |
|                         | 25        | CHAMBERLAIN STREET | 1960         | 8             | AC - Asbestos Cement      | 523            | \$ 104,600           |
|                         | 25        | CHAMBERLAIN STREET | 1960         | 10            | AC - Asbestos Cement      | 1561           | \$ 390,250           |
|                         | 25        | UNDERWOOD STREET   | 1956         | 8             | AC - Asbestos Cement      | 433            | \$ 108,250           |
|                         | 25        | UNDERWOOD STREET   | 1956         | 12            | AC - Asbestos Cement      | 1652           | \$ 495,600           |
|                         |           |                    |              |               |                           | <b>5,531</b>   | <b>\$ 1,371,100</b>  |
| <b>Total</b>            |           |                    |              |               |                           | <b>138,061</b> | <b>\$ 32,335,491</b> |